

Ranger Energy Services
3333 Center Drive
Milliken, CO, 80534
(970) 587-5813 or (970) 587-5824 (Fax)

Job Log

Date: 9/20/2017

Operator: Noble Energy

Well Name: Wells Ranch USX BB #11-10

Legals: NWSE, Section 11, Township 5 North, Range 63 West

API: 05-123-26756

Location: Weld County, Colorado

9/13/2017: MIRU P&A equipment, circulate well, NDWH, NUBOP, TOH with tubing
RU wireline, TIH 4-1/2" CIBP and set at 6,293', TOH, TIH and CDB 2 sxs on top of CIBP
(cement from 6,293' – 6,267'), TOH, RD wireline, load wellbore, test casing to 1000, pressure held
RU hydrotesters, TIH to 2,330', pump 30 sxs of cement, 6.14 bbl. of slurry from 2,330' – 1,934'
TOH, shut well in, SDFN

9/14/2017: RU wireline, TIH and cut casing at 683', TOH, RD wireline
Circulate wellbore, spear and unland casing, NUWH, NUBOP, TOH and LD casing
TIH to 747', pump 10 bbl. of mud flush, pump 327 sxs of cement, 67 bbl. of cement from 747' to 150'
TOH and LD tubing, shut well in with night cap, RDMO

9/20/2017: RU cementing unit, TIH to 150' pump 49 sxs of cement to surface
10 bbl. of slurry from 150' to surface, RD cementing unit and move off, P&A complete

* * * All cement is 15.8 # Class "G" neat cement * * *

Cementing Contractor: Ranger Energy Services

Operator Supervisor: Tyson Hamacher

State Representative: Conor Pesicka

Wireline Contractor: Cased Hole Solutions