

## Weld County, Colorado, Southern Part

### 40—Nunn loam, 1 to 3 percent slopes

#### Map Unit Setting

*National map unit symbol:* 2tln2

*Elevation:* 3,900 to 6,250 feet

*Mean annual precipitation:* 13 to 16 inches

*Mean annual air temperature:* 46 to 54 degrees F

*Frost-free period:* 135 to 160 days

*Farmland classification:* Prime farmland if irrigated

#### Map Unit Composition

*Nunn and similar soils:* 85 percent

*Minor components:* 15 percent

*Estimates are based on observations, descriptions, and transects of the mapunit.*

#### Description of Nunn

##### Setting

*Landform:* Terraces

*Landform position (three-dimensional):* Tread

*Down-slope shape:* Linear

*Across-slope shape:* Linear

*Parent material:* Pleistocene aged alluvium and/or eolian deposits

##### Typical profile

*Ap - 0 to 6 inches:* loam

*Bt1 - 6 to 10 inches:* clay loam

*Bt2 - 10 to 26 inches:* clay loam

*Btk - 26 to 31 inches:* clay loam

*Bk1 - 31 to 47 inches:* loam

*Bk2 - 47 to 80 inches:* loam

##### Properties and qualities

*Slope:* 1 to 3 percent

*Depth to restrictive feature:* More than 80 inches

*Natural drainage class:* Well drained

*Runoff class:* Medium

*Capacity of the most limiting layer to transmit water (Ksat):*

Moderately low to moderately high (0.06 to 0.20 in/hr)

*Depth to water table:* More than 80 inches

*Frequency of flooding:* None

*Frequency of ponding:* None

*Calcium carbonate, maximum in profile:* 7 percent

*Salinity, maximum in profile:* Nonsaline (0.1 to 1.0 mmhos/cm)

*Sodium adsorption ratio, maximum in profile:* 0.5

*Available water storage in profile:* High (about 9.2 inches)

##### Interpretive groups

*Land capability classification (irrigated):* 3e

*Land capability classification (nonirrigated): 4e*  
*Hydrologic Soil Group: C*  
*Ecological site: Loamy Plains (R067BY002CO)*  
*Hydric soil rating: No*

### **Minor Components**

#### **Wages**

*Percent of map unit: 8 percent*  
*Landform: Alluvial fans, terraces*  
*Landform position (three-dimensional): Tread*  
*Down-slope shape: Linear*  
*Across-slope shape: Linear*  
*Ecological site: Loamy Plains (R067BY002CO)*  
*Hydric soil rating: No*

#### **Fort collins**

*Percent of map unit: 5 percent*  
*Landform: Terraces*  
*Landform position (three-dimensional): Tread*  
*Down-slope shape: Linear*  
*Across-slope shape: Linear*  
*Ecological site: Loamy Plains (R067BY002CO)*  
*Hydric soil rating: No*

#### **Haverson, very rarely flooded**

*Percent of map unit: 2 percent*  
*Landform: Alluvial fans, terraces, drainageways*  
*Landform position (three-dimensional): Tread*  
*Down-slope shape: Linear*  
*Across-slope shape: Linear, concave*  
*Ecological site: Overflow (R067BY036CO)*  
*Hydric soil rating: No*

## **Data Source Information**

Soil Survey Area: Weld County, Colorado, Southern Part  
Survey Area Data: Version 15, Sep 22, 2016