

WELL LOG ON BOX ELDER #5

Spudding date: 6/21/57  
Date casing set: 6/21/57  
Date rotary completed: 7/17/57  
Date cable completed:

Location:

NW NW, Section 20-2S-65W, Adams County, Colorado ✓

<u>FROM</u>	<u>TO</u>	<u>FORMATION</u>	<u>REMARKS</u>
0	220	Surface Hole	Ran 5 Jts. 9-5/8" SW Casing, set @ 214' and cemented w/175 Sx. Cement w/2% C.C.
220	5175	Shale	
5175	5350	Sand & Shale	
5350	5715	Shale	
5715	5890	Lime & Shale	
5890	7730	Shale	
7730	7945	Shale & Lime	
7945	8045	Shale	
8045	8125	Lime & Shale	
8125	8212	Shale & Sand	
8212	8222	Sand	
8222	8515	Sand & Shale	
8515	8555	Sand	
8555	8567	Sand & Shale	
8567		Total Depth	Plugged hole w/35 Sx. Cement 240-153' and w/15 Sx. Cement 35'-surface.



Subscribed and sworn to before me this 23rd  
day of July, 19 57.

I certify the above and foregoing to be a true and exact  
copy of the original driller's log on the Box Elder #5.

HERNDON DRILLING COMPANY

[Signature]  
Notary Public  
My commission expires: 1-27-60

By: [Signature]  
Title: Assistant Secretary