

WELLBORE DIAGRAM

UPDATED 1/11/05

COUNTY: LOGAN

FIELD: SPRINGDALESTATE: COLORADO

CASING:

8 5/8" 24# 510' KB

5 1/2" 15.5# J-55 4,965' KB

Safety Valve @ 65'

8 5/8" CSG @ 510' KB

CMT TOP 3340' KB

TUBING DETAIL:

3- 4', 1- 10', 1- 2' 3 1/2" Subs

3 1/2" J-55 8rd EUE 9.3# - 4,716'

Baker FB-1 permanent pkr @ 4,730'

Baker FB-1 permanent set pkr @ 4.730'

EOT @ 4,748'

Squeeze perf's 4,780' - 150 sx (12/14/69)

Perf's 4,865' -4,877' KB 4/ft (12/15/69)

Perf's 4,860' -4,870' KB 4/ft (12/30/99)

PBTD @ 4,928' KB

5 1/2" CSG @ 4,965' KB