



June 14, 2017

Berry Petroleum Company LLC (Berry) is inviting your company to submit a proposal to plug preset conductors on producing and non-producing well pads on the Garden Gulch, Old Mountain, and Long Ridge Mesas in Garfield County near Parachute, Colorado.

Plugging operations will be performed per COGCC rules and procedures:

- Cut the conductor pipe four feet below ground level.
- Fill the conductor pipe with material that is clean, inert, and free from contaminants.
- Seal the conductor pipe with a cement plug and a welded steel plate.
- Backfill the hole to ground level.

Berry will provide clean backfill material – contractor is responsible for loading, hauling, and placing in the conductor – allowing enough room for a concrete plug. One 80-pound sack of pre-mixed concrete furnished by the Contractor can be used for each cement plug. Contractor can use the existing conductor covers to weld on the conductor after it has been cut and filled. Cellar rings can remain in place but must be filled and compacted with clean material and completely covered up. Contractor will tack weld the existing covers on the mouse/rat holes in place and completely cover with dirt.

In addition, on producing pads, Contractor will remove the cellar ring covers from the existing conductors and haul them to a storage site. Upon completion of plugging the conductors, the Contractor will re-install the fence around the producing wells and haul any excess fencing material to a storage site. On producing pads, Contractor will be required to secure a Fire and Safe Work Permit from a Berry representative before any cutting and/or welding takes place.

On non-producing pads, Contractor will remove fencing and cellar ring covers and haul them to a storage site.

Please submit prices on the attached Uniform Bid Sheets. Any questions must be submitted to me via email and I will respond by email. All questions and responses will be shared with all bidders. Bids are due via email to me by 12:00 noon on June 21, 2017. Berry will award work to one or more contractors and work can commence on June 26, 2017.



The attached map shows the locations of the pads – P indicates producing wells on pad and NP indicates no production. The map also shows the locations where the fill material is located.

Berry reserves the right to reject any and all proposals, to enter simultaneously into negotiations with any bidder or any other party, to solicit the submission of additional proposals or to take any other action, which Berry, in its sole discretion, deems necessary or convenient, all without further notice. This request for proposal shall not create any duty, obligation, responsibility or liability of any kind or character upon Berry. Berry reserves the right to place this business on an item by item basis to meet operational objectives.

The provision of this bid shall be governed by the terms and conditions contained in the Berry Petroleum Company LLC Master Services Contract. Nothing contained the RFP, the Contractor's response, and/or any subsequent award shall modify the terms and conditions contained in the Master Service Contract.

Best regards,

Tom Hogelin
Construction Foreman
Berry Petroleum Company LLC
tgh@bry.com
Office 970.285.5207
Cell 970.948.2785