

Document Number:
401418334

Date Received:
10/02/2017

WELL ABANDONMENT REPORT

This form is to be submitted as an Intent to Abandon whenever an abandonment is planned on a borehole. After the abandonment is complete, this form shall again be submitted as a Subsequent Report of the actual work completed. The approved intent shall be valid for six months after the approval date, after that period, a new intent will be required. Attachments required with the Intent to Abandon are wellbore diagrams of the current configuration and the proposed configuration with plugs set.

A Subsequent Report of Abandonment shall indicate the actual work completed. Attachments required with a Subsequent Report are a wellbore diagram showing plugs that were set and casing remaining in the hole, the job summaries from all plugging contractors used, including wireline and cementing (third party verification) and any logs that may have been run during abandonment.

OGCC Operator Number: 24500 Contact Name: Dan Richmond

Name of Operator: PADCO LLC Phone: (918) 630-9912

Address: P O BOX 5275 Fax: _____

City: BEVERLY HILLS State: CA Zip: 90209- Email: dan@dsrinc.net

For "Intent" 24 hour notice required, Name: Sherman, Susan Tel: (719) 775-1111

COGCC contact: Email: susan.sherman@state.co.us

API Number 05-121-10647-00 Well Number: 1

Well Name: BACON UNIT

Location: QtrQtr: SWNE Section: 28 Township: 1S Range: 55W Meridian: 6

County: WASHINGTON Federal, Indian or State Lease Number: _____

Field Name: KENO Field Number: 43900

Notice of Intent to Abandon Subsequent Report of Abandonment

Only Complete the Following Background Information for Intent to Abandon

Latitude: 39.937950 Longitude: -103.544740

GPS Data:
Date of Measurement: 12/14/2007 PDOP Reading: 2.7 GPS Instrument Operator's Name: Darren Veal

Reason for Abandonment: Dry Production Sub-economic Mechanical Problems
 Other _____

Casing to be pulled: Yes No Estimated Depth: 3000

Fish in Hole: Yes No If yes, explain details below

Wellbore has Uncemented Casing leaks: Yes No If yes, explain details below

Details: _____

Current and Previously Abandoned Zones

Formation	Perf. Top	Perf. Btm	Abandoned Date	Method of Isolation	Plug Depth
D SAND	4875	4882			

Total: 1 zone(s)

Casing History

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bot	Cement Top	Status
SURF	12+1/4	8+5/8	25#	150	75	150	0	VISU
1ST	7+7/8	5+1/2	14# & 15#	5,020	150	5,020	3,540	CBL

Plugging Procedure for Intent and Subsequent Report

CIBP #1: Depth 4840 with 2 sacks cmt on top. CIBP #2: Depth _____ with _____ sacks cmt on top.
CIBP #3: Depth _____ with _____ sacks cmt on top. CIBP #4: Depth _____ with _____ sacks cmt on top.
CIBP #5: Depth _____ with _____ sacks cmt on top.

NOTE: Two(2) sacks cement required on all CIBPs.

Set 40 sks cmt from 3050 ft. to 2900 ft. Plug Type: STUB PLUG Plug Tagged:
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:
Set _____ sks cmt from _____ ft. to _____ ft. Plug Type: _____ Plug Tagged:

Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
Perforate and squeeze at _____ ft. with _____ sacks. Leave at least 100 ft. in casing _____ CICR Depth
(Cast Iron Cement Retainer Depth)

Set 50 sacks half in. half out surface casing from 200 ft. to 100 ft. Plug Tagged:

Set 10 sacks at surface

Cut four feet below ground level, weld on plate Above Ground Dry-Hole Marker: Yes No

Set _____ sacks in rat hole Set _____ sacks in mouse hole

Additional Plugging Information for Subsequent Report Only

Casing Recovered: _____ ft. _____ inch casing Plugging Date: _____
of _____

*Wireline Contractor: _____ *Cementing Contractor: _____

Type of Cement and Additives Used: _____

Flowline/Pipeline has been abandoned per Rule 1103 Yes No *ATTACH JOB SUMMARY

Technical Detail/Comments:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Dan Richmond

Title: Field Operations Supervis Date: 10/2/2017 Email: dan@dsrinc.net

Based on the information provided herein, this Well Abandonment Report (Form 6) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: SUTPHIN, DIRK Date: 10/24/2017

CONDITIONS OF APPROVAL, IF ANY: _____

Expiration Date: 4/23/2018

COA Type	Description
	1) Provide 48 hour notice of MIRU via electronic Form 42. 2) Shoe plug: Tag plug 50' above surface casing shoe or cement to surface. 3) Surface plug: Cement from 50' to surface. 4) Properly abandon flowlines per Rule 1103. File Form 42 when done.
	Bradenhead: Prior to starting plugging operations a bradenhead test shall be performed. 1) If, before opening the bradenhead valve, the beginning pressure is greater than 25 psi, sampling is required. 2) If pressure remains at the conclusion of the test, or if any liquids were present during the test, sampling is required. Sampling shall comply with Operator Guidance - Bradenhead Testing and Reporting Instructions, Appendix A: Liquid and Gas Sampling. The Form 17 shall be submitted within 10 days of the test.

Attachment Check List

Att Doc Num	Name
401418334	FORM 6 INTENT SUBMITTED
401418380	WELLBORE DIAGRAM
401418382	WELLBORE DIAGRAM
401418397	CEMENT BOND LOG

Total Attach: 4 Files

General Comments

User Group	Comment	Comment Date
Engineer	Stub plug is required where casing is pulled. Estimated Depth is 3000'.	10/24/2017
Public Room	Document verification complete 10/03/17	10/03/2017

Total: 2 comment(s)