

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401403134

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10542

Contact Name: PAUL GOTTLÖB

Name of Operator: CUB CREEK ENERGY

Phone: (720) 420-5747

Address: 200 PLAZA DRIVE SUITE 100

Fax:

City: HIGHLANDS State: CO Zip: 80129

API Number 05-123-42778-00

County: WELD

Well Name: Litzenberger

Well Number: 6

Location: QtrQtr: SENE Section: 8 Township: 3N Range: 68W Meridian: 6

Footage at surface: Distance: 1928 feet Direction: FNL Distance: 1154 feet Direction: FEL

As Drilled Latitude: 40.242330 As Drilled Longitude: -105.021730

## GPS Data:

Date of Measurement: 09/15/2017 PDOP Reading: 2.2 GPS Instrument Operator's Name: Scott Sherard

\*\* If directional footage at Top of Prod. Zone Dist.: 1108 feet. Direction: FNL Dist.: 460 feet. Direction: FEL

Sec: 8 Twp: 3N Rng: 68W

\*\* If directional footage at Bottom Hole Dist.: 1090 feet. Direction: FNL Dist.: 460 feet. Direction: FWL

Sec: 8 Twp: 3N Rng: 68W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 05/18/2017 Date TD: 06/18/2017 Date Casing Set or D&amp;A: 06/20/2017

Rig Release Date: 09/10/2017 Per Rule 308A.b.

## Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 11984 TVD\*\* 7070 Plug Back Total Depth MD 11949 TVD\*\* 7070

Elevations GR 5082 KB 5099 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

## List Electric Logs Run:

CBL, Mud, MWD/LWD, (Triple Combo in API 05-123-42781)

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	43	0	80	400	0	80	VISU
SURF	13+1/2	9+5/8	36	0	1,541	406	0	1,541	VISU
1ST	8+1/2	5+1/2	17	0	11,974	1,840	60	11,974	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,629		NO	NO	
SUSSEX	4,102		NO	NO	
SHARON SPRINGS	7,074		NO	NO	
NIOBRARA	7,321		NO	NO	

Comment:

The stated footages for the TPZ are at MD 9015', TVD 7151', if changed upon completion this will be updated on the Form 5A.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: PAUL GOTTLOB

Title: Regulatory & Engin. Tech. Date: \_\_\_\_\_ Email: paul.gottlob@iptenergyservices.com

### Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401407648	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401441423	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401406922	LAS-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401406923	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401406924	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401406925	PDF-MUD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401407653	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401433326	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401435036	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)