



SRC ENERGY

**Operator:** SRC Energy  
**Well Name:** Avex #42-10D  
**Legal:** SWNE Section 10, Township 4N, Range 68W  
**Location:** Weld County, CO  
**API:** 05-123-34998

Deepest Water Well Within 1  
Mile = 260'





### Wellbore History

Spud Date: 09/16/2012  
Surf Csg: 8.625", 24# @ 650' – 175 sks  
Prod Csg: 4.5", 11.6# @ 7795' – 730 sks  
TOC: 1870' from CBL  
Perfs: CODELL: 7221'-7237'

### Actual P&A Procedure

Set retainer@ 7146'  
Squeeze perfs w/ 15 sx  
Set 35 sx on top of retainer (461' plug)  
Pmp 18 sx @ 4000' (237' plug)  
Cut Casing @ 700'  
Pmp 317 sx @ 768' to surface

### Key

-  Existing Cement Coverage
-  Retainer
-  Cement Pumped
-  CIBP

