

FORM  
2  
Rev  
08/16

State of Colorado  
Oil and Gas Conservation Commission  
1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:  
401306798

APPLICATION FOR PERMIT TO:

Drill  Deepen  Re-enter  Recomplete and Operate

Date Received:  
06/29/2017

TYPE OF WELL OIL  GAS  COALBED  OTHER \_\_\_\_\_  
ZONE TYPE SINGLE ZONE  MULTIPLE ZONES  COMMINGLE ZONES

Refilling   
Sidetrack

Well Name: SHUMAKER Well Number: 8-18HZ  
Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP COGCC Operator Number: 47120  
Address: P O BOX 173779  
City: DENVER State: CO Zip: 80217-3779  
Contact Name: CRAIG RICHARDSON Phone: (720)929-6092 Fax: (720)929-7093  
Email: CRAIG.RICHARDSON@ANADARKO.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: SWSE Sec: 8 Twp: 1N Rng: 68W Meridian: 6  
Latitude: 40.058907 Longitude: -105.026504

Footage at Surface: 231 Feet FNL/FSL FSL 2334 Feet FEL/FWL FEL

Field Name: WATTENBERG Field Number: 90750

Ground Elevation: 5107 County: WELD

GPS Data:  
Date of Measurement: 03/02/2017 PDOP Reading: 1.2 Instrument Operator's Name: ROB WILSON

If well is  Directional  Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
50 FSL 722 FEL 50 FNL 839 FEL  
Sec: 8 Twp: 1N Rng: 68W Sec: 8 Twp: 1N Rng: 68W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership:  Fee  State  Federal  Indian

The Surface Owner is:  is the mineral owner beneath the location.  
(check all that apply)  is committed to an Oil and Gas Lease.  
 has signed the Oil and Gas Lease.  
 is the applicant.

The Mineral Owner beneath this Oil and Gas Location is:  Fee  State  Federal  Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

**LEASE INFORMATION**

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 1 North, Range 68 West, 6th P.M.  
Section 8: NW/4, SW/4NE/4, SE/4, And other lands.

Total Acres in Described Lease: 5844 Described Mineral Lease is:  Fee  State  Federal  Indian

Federal or State Lease # \_\_\_\_\_

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

**CULTURAL DISTANCE INFORMATION**

Distance to nearest:

Building: 2438 Feet  
 Building Unit: 2438 Feet  
 High Occupancy Building Unit: 4527 Feet  
 Designated Outside Activity Area: 5280 Feet  
 Public Road: 215 Feet  
 Above Ground Utility: 330 Feet  
 Railroad: 1308 Feet  
 Property Line: 201 Feet

**INSTRUCTIONS:**

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).  
 - Enter 5280 for distance greater than 1 mile.  
 - Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.  
 - Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

**DESIGNATED SETBACK LOCATION INFORMATION**

Check all that apply. This location is within a:  Buffer Zone  
 Exception Zone  
 Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit  
 - Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
 - Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: \_\_\_\_\_

**SPACING and UNIT INFORMATION**

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 117 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 521 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

**SPACING & FORMATIONS COMMENTS**

Spacing Unit: 1N 68W Sec 5: SESE; Sec. 8: E2E2; Sec.17: NENE

**OBJECTIVE FORMATIONS**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		240	GWA

## DRILLING PROGRAM

Proposed Total Measured Depth: 13648 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 238 Feet  No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H<sub>2</sub>S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H<sub>2</sub>S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type:  Annular Preventor  Double Ram  Rotating Head  None

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Please see Comments section. Disposal description will not fit in space provided.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: \_\_\_\_\_ or Document Number: \_\_\_\_\_

## CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	42.1	0	40	30	40	0
SURF	13+1/2	9+5/8	36	0	1500	590	1500	0
1ST	7+7/8	5+1/2	17	0	13638	1602	13638	

Conductor Casing is NOT planned

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- Rule 318A.a. Exception Location (GWA Windows).
- Rule 318A.c. Exception Location (GWA Twinning).

## RULE 502.b VARIANCE REQUEST

Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

### OTHER LOCATION EXCEPTIONS

Check all that apply:

Rule 318.c. Exception Location from Rule or Spacing Order Number \_\_\_\_\_

Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

### OPERATOR COMMENTS AND SUBMITTAL

Comments

Please see the 318A.a. & 318.A.c. exception approval attached in the SUA memo on page 1, section 1; and Exhibit A. KMG has obtained a signed Surface Use Agreement from the surface owner that contains language specific to the location of the proposed well. The Memo of SUA includes evidence of this on Page 1, Section 1. Additionally, a site specific location map is part of the signed agreement and included as Exhibit A of the SUA Memo. Please consider the surface owner's project location map (location of proposed wells) as a waiver to these rules. Should you have any questions, please contact our office.

Flow Lines: 20 flow lines will flow to the production facility location. During production, flow direction in the flow lines is from the well head to the production facility. The size of flow lines is typically 2". Flow lines will be constructed from steel pipe, buried, and will equal the distance between the well heads and the tank battery, approximately 300'.

20 fuel gas supply lines will also be installed from the well head to the production facility. During operation flow direction in the supply lines will be from the production facility to the well head. The size of the supply lines is typically 1". Supply lines will be constructed from poly or steel pipe, buried, and will equal the distance between the well heads and the tank battery, approximately 300'.

Gas lift lines are also occasionally installed (one per well) from the well head to the production facility. During operation flow direction in the gas lift lines will be from the production facility to the well head. The size of the gas lift lines is typically 2". Gas lift lines will be constructed from steel pipe, buried, and will equal the distance between the well heads and the tank battery, approximately 300'.

The nearest building unit is located over 1000' away from this well, therefore it is not within a Designated Setback Location and is exempt from 604.c.

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent possible, at which point they will either be land applied or taken to a licensed, commercial disposal site; the decision will be based upon laboratory analysis of fluids. KMG will reuse oil-based drilling fluids to the maximum extent possible, at which point they will be returned to the fluids manufacturer for reconditioning or disposal at a licensed, commercial disposal site.

Cuttings disposal: Water-based cuttings will be disposed of using a Centralized E&P Waste Management facility or a private spread field, depending on what is feasible at the time of drilling. Oil-based cuttings will be disposed of offsite and at a licensed, commercial disposal site.

This proposed well will have a treated interval less than one hundred fifty (150) feet from the treated interval of another well and is subject to COGCC Rule 317.r.

The following well(s) belong to another operator and will have treated intervals within one hundred fifty (150) feet of this proposed well anti-collision waiver not required:  
WOOLLEY 44-8

The following well(s) belong to Kerr-McGee and will have treated intervals within one hundred fifty (150) feet of this proposed well:

TALLGRASS 8-8  
TALLGRASS 1-8  
SHUMAKER 8-9HZ  
SHUMAKER 8-8HZ

This application is in a Comprehensive Drilling Plan       No       CDP #: \_\_\_\_\_

Location ID:       452527      

Is this application being submitted with an Oil and Gas Location Assessment application?       Yes      

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name:       CRAIG RICHARDSON

Title: REGULATORY ANALYST II

Date: 6/29/2017

Email: DJREGULATORY@ANDARKO

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_



Director of COGCC

Date: 11/29/2017

Expiration Date: 11/28/2019

API NUMBER

05 123 45952 00

### Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

#### COA Type

#### Description

	<ol style="list-style-type: none"><li>1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad.</li><li>2) Comply with Rule 317.j. and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.</li><li>3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered.</li></ol>
	<p>Bradenhead tests shall be performed according to the following schedule and the Form 17 submitted within 10 days of each test:</p> <ol style="list-style-type: none"><li>1) Within 60 days of rig release and prior to stimulation and</li><li>2) If a delayed completion, 6 months after rig release and prior to stimulation.</li><li>3) Within 30 days after first production, as reported on Form 5A.</li></ol>

## Best Management Practices

No	<b>BMP/COA Type</b>	<b>Description</b>
1	Drilling/Completion Operations	Kerr-McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
2	Drilling/Completion Operations	Anti-Collision: Kerr-McGee will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within one hundred fifty (150) feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators within one hundred fifty (150) feet prior to drilling.
3	Drilling/Completion Operations	317.p Logging Program: One of the first wells drilled on the pad will be logged with Cased-hole Pulsed Neutron Log with Gamma Ray Log the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The Form 5, Completion Report, for each well on the pad will list all logs run in that well and have those logs attached. The Form 5 for each well shall clearly state "No open-hole logs were run" and shall reference the Rule 317.p Exception granted for the well.

Total: 3 comment(s)

## Applicable Policies and Notices to Operators

Policy
Notice Concerning Operating Requirements for Wildlife Protection. <a href="http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf">http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf</a>
Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area. <a href="http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf">http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf</a>

## Attachment Check List

Att Doc Num	Name
1696893	STIMULATION SETBACK CONSENT
401306798	FORM 2 SUBMITTED
401315320	DEVIATED DRILLING PLAN
401315321	WELL LOCATION PLAT
401318826	OffsetWellEvaluations Data
401318851	DIRECTIONAL DATA
401326735	PROPOSED SPACING UNIT
401341329	OPEN HOLE LOGGING EXCEPTION
401341330	SURFACE AGRMT/SURETY
401350313	EXCEPTION LOC REQUEST
401470222	OFFSET WELL EVALUATION

Total Attach: 11 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed.	11/17/2017
Engineer	Offset wells evaluated.	10/09/2017
Engineer	On hold- Crestone well distance needs further review. Stimulation setback consent may be needed.  Stimulation setback consent is not required.	10/09/2017
Permit	Operator requested Exception to Open Hole Logging Rule 317.p. See attached. The Surface Use Agreement has waivers for Rule 318A.a & 318A.c. See page 1, Section 1 & Exhibit A. With operator concurrence corrected Mineral lease and total acres. Permitting Review Complete.	10/02/2017
Permit	An LGD task has been created for the Town of Erie LGD.	08/03/2017
Permit	Passed Completeness.	07/28/2017
Permit	Returned to draft for: -Exception Location Waiver Attachment edits. -"Submit" tab comments edit	07/20/2017
Permit	Returned to draft for: -Open Hole Logging Exception Attachment is incomplete. -Exception Location Waiver Attachment is incomplete.	07/11/2017

Total: 8 comment(s)