

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400926193

Date Received:

11/06/2015

DRILLING COMPLETION REPORT

Per Rule 308A, this form and all required attachments shall be submitted after completing the drilling operations to drill, sidetrack, or deepen a wellbore and after changing the casing and cement configuration of a wellbore. If any attempt has been made to test, complete, or produce the well, the operator shall also submit a Form 5A (Completed Interval Report) per Rule 308B. If the well has been plugged, the operator shall also submit a Form 6 (Well Abandonment Report) per Rule 311.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 47120

Contact Name: ILA BEALE

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6408

Address: P O BOX 173779

Fax:

City: DENVER State: CO Zip: 80217-

API Number 05-123-41910-00

County: WELD

Well Name: GE POWERS

Well Number: 29N-26HZ

Location: QtrQtr: NWNW Section: 23 Township: 2N Range: 65W Meridian: 6

Footage at surface: Distance: 400 feet Direction: FNL Distance: 1320 feet Direction: FWL

As Drilled Latitude: 40.130242 As Drilled Longitude: -104.635932

GPS Data:

Date of Measurement: 08/10/2015 PDOP Reading: 2.0 GPS Instrument Operator's Name: Sergio Del Carmen

** If directional footage at Top of Prod. Zone Dist.: 1023 feet Direction: FNL Dist.: 920 feet Direction: FWL

Sec: 23 Twp: 2N Rng: 65W

** If directional footage at Bottom Hole Dist.: 414 feet Direction: FNL Dist.: 928 feet Direction: FWL

Sec: 26 Twp: 2N Rng: 65W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 08/03/2015 Date TD: 08/28/2015 Date Casing Set or D&A: 08/30/2015

Rig Release Date: 09/16/2015 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 12210 TVD** 6975 Plug Back Total Depth MD 12198 TVD** 6976

Elevations GR 4890 KB 4910

Digital Copies of ALL Logs must be Attached per Rule 308A ☐

List Electric Logs Run:

CBL, MWD, (CNL in 123-41914, IND in 123-20960, 123-19573)

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42.1	0	60	24	0	60	VISU
SURF	13+1/2	9+5/8	36	0	1,846	738	0	1,846	VISU
1ST	8+1/2	5+1/2	17	0	12,201	1,730	38	12,201	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,533				
SHARON SPRINGS	7,005				
NIOBRARA	7,095				

Operator Comments

Due to anti-collision needs and the variability of directional drilling, our as-drilled BHL could be different than the permitted. Per Rule 317.p & the Open Hole Logging Exception(doc#400846362), the CNL was run on the GE POWERS 3N-W26HZ (123-41914)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: ILA BEALE

Title: STAFF REG. SPECIALIST Date: 11/6/2015 Email: rscdjpostdrill@anadarko.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400926242	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400932190	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400926193	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400926233	PDF-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400926239	PDF-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400926240	LAS-MEASUREMENT/LOGGING WHILE DRILLING	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400931246	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineering Tech	<ul style="list-style-type: none">• Corrected the comments in the Drilling/Submit tab• Corrected the "Cement Top" for the first string from 47' to 38' per the Cement Bond Log CNL meets the requirement of the Open Hole Logging Exception	12/05/2017
Permit	Changed Logs Run to CBL, MWD, (CNL in 123-41914, IND in 123-20960, 123-19573) Changed Rule 371.p to Rule 317.p, 3C-26HZ to 3N-W26HZ in Submit tab	12/04/2017

Total: 2 comment(s)