

FORM
5Rev
09/14

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401433693

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 69175

Contact Name: Ally Ota

Name of Operator: PDC ENERGY INC

Phone: (303) 831-3931

Address: 1775 SHERMAN STREET - STE 3000

Fax: (303) 860-5838

City: DENVER State: CO Zip: 80203

API Number 05-123-42830-00

County: WELD

Well Name: Dunn

Well Number: 7L-201

Location: QtrQtr: SWSW Section: 7 Township: 5N Range: 64W Meridian: 6

Footage at surface: Distance: 765 feet Direction: FSL Distance: 981 feet Direction: FWL

As Drilled Latitude: 40.408463 As Drilled Longitude: -104.598271

GPS Data:

Date of Measurement: 03/06/2017 PDOP Reading: 1.6 GPS Instrument Operator's Name: Devin Arnold

** If directional footage at Top of Prod. Zone Dist.: 460 feet. Direction: FSL Dist.: 1230 feet. Direction: FWL

Sec: 7 Twp: 5N Rng: 64W

** If directional footage at Bottom Hole Dist.: 200 feet. Direction: FNL Dist.: 1189 feet. Direction: FWL

Sec: 6 Twp: 5N Rng: 64W

Field Name: WATTENBERG

Field Number: 90750

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 12/13/2016 Date TD: 12/20/2016 Date Casing Set or D&A: 12/22/2016

Rig Release Date: 02/22/2016 Per Rule 308A.b.

Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 16789 TVD** 6714 Plug Back Total Depth MD 16753 TVD** 6714

Elevations GR 4625 KB 4648

Digital Copies of ALL Logs must be Attached per Rule 308A ☒

List Electric Logs Run:

CBL, MWD, (DIL in 123-13053)

CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	9+5/8	36	0	1,671	770	0	1,671	VISU
1ST	8+1/2	5+1/2	20	0	16,767	2,395	0	16,767	VISU

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	3,581				
SUSSEX	4,279				
SHANNON	4,999				
SHARON SPRINGS	6,531				
NIOBRARA	6,704				

Comment:

Open hole logging exception; no open hole logs were run on this pad; cased hole neutron was run on Dunn 7L-341 (API: 123-42832)

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Cassie Gonzalez

Title: Regulatory Contractor

Date: _____

Email: cassie.gonzalez@pdce.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401439498	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401433915	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401433893	PDF-CBL 1ST RUN	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401433902	LAS-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401433904	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401433905	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401433907	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401433908	PDF-MWD/LWD	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401433914	WELLBORE DIAGRAM	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401433918	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401471895	LAS-CBL 1ST RUN	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)