



SRC ENERGY

**Operator:** SRC Energy  
**Well Name:** Berry 22-02  
**Legal:** NWNE, Section 22, Township 6N, Range 66W  
**Location:** Weld County, CO  
**API:** 05-123-17239

Deepest Water Well Within 1  
Mile = 605'





## Wellbore History

Spud Date: 8/6/1993  
Surf Csg: 8.625", 24# @ 493' – 460 sx  
• Remedial csg cmt @ 700' – 300 sx  
Prod Csg: 4.5", 11.6# @ 7315' – 220 sx  
TOC: 6166' (CBL)  
Perfs: NIOBRARA: 6998' – 7098'  
CODELL: 7184' – 7200'

## Actual P&A Procedure

Set CIBP @ 6948'  
Pmp 20 sx on top of CIBP (264' plug)  
Perforate @ 2500'  
Set CICR @ 2400'  
Squeeze perfs w/ 125 sx  
Set 10 sx on top of CICR (132' plug)  
Pmp 75 sx @ 865' to surface

## Key

-  Existing Cement Coverage
-  CICR
-  Cement Pumped
-  CIBP

