



Bison Oil Well Cementing Single Cement Surface Pipe

Date: 8/14/2017
Invoice #: 666184
API#: 05-123-44228
Foreman: Nick Vigil

Customer: Anadarko Petroleum Corporation
Well Name: Rocky 20N-33HZ

County: Weld
State: Colorado
Sec: 14
Twp: 1N
Range: 67W

Consultant: Sean
Rig Name & Number: Cartel 88
Distance To Location: 32 Miles
Units On Location: 4023/4044/4045
Time Requested: 6:15
Time Arrived On Location: 8:00
Time Left Location:

WELL DATA	Cement Data
Casing Size OD (in) : 9.625	Cement Name: BFN III
Casing Weight (lb) : 36.00	Cement Density (lb/gal) : 14.2
Casing Depth (ft.) : 1,868	Cement Yield (cuft) : 1.49
Total Depth (ft) : 1878	Gallons Per Sack: 7.48
Open Hole Diameter (in.) : 13.50	% Excess: 5%
Conductor Length (ft) : 80	Displacement Fluid lb/gal: 8.3
Conductor ID : 15.25	BBL to Pit:
Shoe Joint Length (ft) : 44	Fluid Ahead (bbls): 30.0
Landing Joint (ft) : 10	H2O Wash Up (bbls): 20.0
Max Rate: 8	Spacer Ahead Makeup
Max Pressure: 2000	Dye in second 10 bbl

Casing ID 8.921	Casing Grade J-55 only used
Calculated Results	Displacement: 141.78 bbls
cuft of Shoe 19.10 cuft (Casing ID Squared) X (.005454) X (Shoe Joint ft)	(Casing ID Squared) X (.0009714) X (Casing Depth + Landing Joint - Shoe Joint)
cuft of Conductor 61.05 cuft (Conductor Width Squared) -(Casing Size OD Squared) X (.005454) X (Conductor Length ft)	Pressure of cement in annulus
cuft of Casing 917.54 cuft (Open Hole Squared)-(Casing Size Squared) X (.005454) X (Casing Depth - Conductor Length)	Hydrostatic Pressure: 1378.02 PSI
Total Slurry Volume 997.69 cuft (cuft of Shoe) + (cuft of Conductor) + (cuft of Casing)	Pressure of the fluids inside casing
bbls of Slurry 177.69 bbls (Total Slurry Volume) X (.1781)	Displacement: 786.47 psi
Sacks Needed 670 sk (Total Slurry Volume) ÷ (Cement Yield) X (% Excess Cement)	Shoe Joint: 32.46 psi
Mix Water 119.25 bbls (Sacks Needed) X (Gallons Per Sack) ÷ 42	Total 818.93 psi
	Differential Pressure: 559.09 psi
	Collapse PSI: 2020.00 psi
	Burst PSI: 3520.00 psi
	Total Water Needed: 311.03 bbls

X
Authorization To Proceed

Customers hereby acknowledges and specifically agrees to the terms and condition on this work order, including, without limitation, the provisions on this work order.

X 8/14/17
Date

Rocky 20N-33HZ

