




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS
CONSERVATION COMMISSION
295-8

(Indicate nature of data by checking below)

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report x

Following is a ~~(notice of intention to do work)~~ August 5, 1952
 (report of work done) (On-land) (patented) described as follows:

| Colorado | Logan | Luft |
|------------|---------------------|-------------------------------|
| State | County | Field |
| <u>3</u> | <u>C. Luft, Jr.</u> | <u>SE/4 Sec 17</u> |
| (Well No.) | (Lease) | (Sec. and $\frac{1}{4}$ Sec.) |
| | | <u>8N</u> |
| | | (Twp.) |
| | | <u>53W</u> |
| | | (Range) |
| | | <u>-</u> |
| | | (Meridian) |

The well is located 330 ft. (N) of south line and 330 ft. (E) of west line
(S) (W)

The elevation above sea level is 4175 D.F. ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

7-14-52 Spudded. Ran and cemented 8 5/8" casing at 601' with 325 sacks.
 7-18-52 Drilled to 4942'. Sample top 'Muddy' sandstone 4821. 4821-23 sand Trace of pin point porosity, light oil stain. Good S.F. & ECF. 4823-26 sand as above with tight streaks. 4826-32 sand, pin point porosity to trace of visible porosity. Light oil stain, good SF and ECF. Shale streaks. 4832-52 sand and shale, trace of visible porosity. No show. 4928-42 Sand, trace of fair visible porosity. No shows.
 7-21-52 Ran Schlumberger.
 Cemented 4 1/2" casing at 4898 with 150 sacks. Waiting on cable tools.
 7-28-52 Swabbed hole dry. Loaded hole with 25 barrels of oil. Perforated 4829-30 with 4 10-gm jet shots. Perforated 4820-29 with 36 10-gm jet shots. Ran tubing. Swabbed 25 barrel load oil and 16 barrel new oil with trace of water in 7 hours.
 7-30-52 Installing pumping equipment.
 8-4-52 Pumped 135 barrels of oil, no water in 24 hours. Complete. (continued)
 Approved: AUG 7 1952 Company Shell Oil Company

J. J. Zwick
 Director
 Address Denham Bldg., Denver, Colorado
 By [Signature]
 Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

17-8N-53W

Schlumberger Formation Tops:

| | |
|-----------|------|
| Niobrara | 4040 |
| Timpas | 4374 |
| Greenhorn | 4590 |
| 'Muddy' | 4818 |
| Dakota | 4927 |