

075-05911

OIL AND GAS CONSERVATION COMMISSION OF THE STATE OF COLORADO

RECEIVED APR 11 1963

OIL & GAS CONSERVATION COMMISSION



PLUGGING RECORD

INSTRUCTIONS

Within thirty (30) days after the plugging of any well, the owner or operator thereof shall file this form in duplicate for wells on Patented or Federal lands, and in triplicate for wells on State lands, give a detailed account of the manner in which the abandonment or plugging work was carried out, including the nature and quantities of materials used in plugging and the location and extent (by depths) of the plugs of different materials; records of the amount, size and location (by depths) of casings and junk left in the well; and a detailed statement of the volume and weight of mud fluid used.

Operator Skelly Oil Company Field Dale North Wildcat -
Lease Name L. E. Rieke Well No. 1 County Logan
Location NW SW/4 SW/4 Section 12 Township 8N Range 53W Meridian -
990 feet from South Section line and 330 feet from West Section Line
N or S E or W

TOTAL DEPTH 4846' DATE OF PLUGGING March 29, 1963

DETAILS OF WORK

PLUGGED WELL AS FOLLOWS:

- TD - 4846-4800' - Filled with sand
4800-4763' - 37' cement plug
4763- 262' - 10# drilling mud
262- 252' - Rock bridge
252- 235' - 17' cement plug
235- 16' - 10# drilling mud
16'-Surface - 16' cement plug

Table with 2 columns and 7 rows: DVR, WRS, HHM, JAM, FJP, JJD, FILE. JAM, FJP, and JJD have checkmarks.

240' of 10-3/4" OD 29# Armco SWSJ surface casing set at 252' was left in the hole.
Approximately 810' of 5 1/2" OD 14# & 17# production casing set at 4839' was left in the hole.

Location checked on 6/11/63 P+A O, 1 well Jim



I/we hereby swear (or affirm) that the statements herein made are a full and correct report:

Approved: W. R. Smith Director
Company Skelly Oil Company Date April 10, 1963
Address McCook, Nebraska Phone No. 345-3510
By G. F. Ban (Signature) Title Dist. Supt.