

COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report x _____

Following is a ~~(notice of intention to do work)~~ May 27 19 53
 (report of work done) (On-land)
 (patented) described as follows:

Colorado Logan Dale
 State County Field

3 W. E. Tetsell Jr. SE/4 14 8N 53W
 (Well No.) (Lease) (Sec. and $\frac{1}{4}$ Sec.) (Twp.) (Range) (Meridian)

The well is located 330 ft. (N) of N. Line and 330 ft. (E) of
(S) (W)

West Line of SE/4, Section 14-8N-53W.

The elevation above sea level is 4121 ft.

Details of Plan of Work: (State names of and expected depths to objective sands:
 Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cement-
 ing points, and all other important proposed work.)

- 4-6-53 Spudded. Ran and cemented 8 5/8" casing at 596 feet with 275 sacks.
 4-12-53 Drill Stem Test #1 4682-91 open 1 hour. Gas in 3 minutes at 150 MCFPD. Deminishing
 to weak blow at end of test. Recovered 3900' light gas cut oil. Ran Schlumberger.
 Cemented 5 1/2" casing at 4683 with 100 sacks plus 4% jel.
 4-20-53 Drilled cement plug from 4615 to 83.
 4-21-53 Waiting on lead lines.
 5-25-53 Flowed 116 barrels oil 294 MCF Gas, in 24 hours thru 28/64" choke. GOR 2534.

Complete
(Over)

Approved: MAY 27 1953

J. J. Tetsell
 Director at

Company Shell Oil Company

Address Denham Building, Denver, Colorado

By J. J. Tetsell

Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.

Schlumberger Formation Tops: