



OFFICE OF STATE OIL INSPECTOR
 SUNDRY NOTICES AND REPORTS OF WELLS
 LOCATED ON PRIVATE LANDS

142-e

(Indicate nature of data by checking below)

- Notice of intention to drill _____
- Notice of intention to change plans _____
- Notice of date for test of water shut-off _____
- Report on result of test of water shut-off _____
- Notice of intention to re-drill or repair well _____
- Notice of intention to clean out well _____
- Statement of shooting _____
- Statement of perforating _____
- Notice to pull or otherwise alter casing _____
- Notice of intention to abandon well _____
- Report of work done on well since previous report _____
- SUBSEQUENT REPORT OF WORKOVER _____

OCTOBER 23, 1951

Following is a ~~(notice of intention to do work)~~ (patented) (report of work done) described as follows:

COLORADO	LOGAN	YENTER POOL		
State	County	Field		
2	YENTER	3 NE/4	8 N	54 W
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)	(Twp.)	(Range) (Meridian)

The well is located 330 ft. (N) of S LINE and 990 ft. (E) of W LINE

The elevation above sea level is 4373 ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

May 28, 1951. Moved in and rigged up Cable Tools.
 International Cementers pumped 117 BW & 35 Bbls. Rotary mud and displaced to bottom to kill well.
 Pulled Tubing and drilled and underreamed to TD 5253'.
 Ran 61' of 4 1/2" Liner Pipe equipped with Baker Washdown Whirler Guide Shoe. Set at 5253' with 15 Sax Slo-set Cement. Resqueezed with 6 Sax Cement. Lane-Wells perforated interval 5234-5235 W/ 4 Jet shots. Well kicked off flowing. G O R 1977 to 1.

July 21, 1951.- Moved in and rigged up Cable Tools. Killed well W/125 Bbls Water. Squeezed off perforations 5234-5235. Drilled out Cement to 5241', and perforated interval 5234-5235 W/8 Jet shots. Ran Tubing & Rods and hung well on Beam.
 August 16, 1951.- Final Report- Well produced 86 BO & 64 BW in 24 hours through 1/4" Ckoke & 16x54 SPM. Associated G O R was 1200 Cu. ft. per Bbl.

Approved: OCT 29 1951

[Signature]
 Director

Company: BRITISH-AMERICAN OIL PROD. COMPANY

Address: BOX 620, CASPER, WYOMING.

By: *[Signature]*
 C. Wm. Evelyn Jr.
 Title: District Superintendent.

Submit reports of proposed work, for approval, on this form in duplicate.