



OFFICE OF STATE OIL INSPECTOR
SUNDRY NOTICES AND REPORTS OF WELLS
LOCATED ON PRIVATE LANDS

117-3

(Indicate nature of data by checking below)

Notice of intention to drill.....X.....
Notice of intention to change plans.....
Notice of date for test of water shut-off.....
Report on result of test of water shut-off.....
Notice of intention to re-drill or repair well.....
Notice of intention to clean out well.....
Statement of shooting.....
Statement of perforating.....
Notice to pull or otherwise alter casing.....
Notice of intention to abandon well.....
Report of work done on well since previous report.....

Jan. 4th. 19 51

Following is a (notice on intention to do work) (On land)
(~~reports of work done~~) (~~potentially~~) described as follows:

COLORADO	LOGAN	YENTER BLOCK
State	County	Field
Two (2)	Yenter, L.A.	3 NE 4 SW 54W
(Well No.)	(Lease)	(Sec. and 1/4 Sec.) (Twp.) (Range) (Meridian)

The well is located 330 ft. (N) of S.L. and 990 ft. (E) of W.L.
(S) (E)
Lot 6 Sec. 3

The elevation above sea level is 4582 ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

to drill W/Rotary Tools and test subject well to the "J" sand of the Granerous sand series expected at approximately 5222'.
SURFACE CASING to be 8 5/8" OD 32# T&C, set at approximately 250' W/175Sks.
PRODUCTION STRING to be 5 1/2" OD 15.5# set on or through the producing zone-
Cement string W/ approximately 120 Sks. 175 SK
TESTING; Test the "D" sand if it runs structurally high.
CONVENTIONAL CORE 10' into the "J" sand & DST all significant gas and oil shows.
LOGGING; (1) Run Schlumberger Electric Log from under surface Casing to total depth.
SAMPLES; 10' intervals from 4200-5050. 5' intervals from 5050 to total depth.
DEPTH MEASUREMENT; S.L.M. of drill pipe at approximately 4000' & prior to coring DST and at TD.
COMPLETION; To be determined by DST and Geological evaluation.

Approved: Jan. 17, 1951
State Oil Inspector

Company The British American Oil Prod. Co.
P.O. Box 620
Address Casper, Wyoming.
By C. Wm. Evelyn Jr. / gdt
G. Wm. Evelyn Jr.
Title District Superintendant.

Submit reports of proposed work, for approval, on this form in Duplicate.