


OIL AND GAS CONSERVATION COMMISSION
OF THE STATE OF COLORADO

SUNDRY NOTICES AND REPORTS ON WELLS

OIL & GAS
CONSERVATION COMMISSION

INSTRUCTIONS



Notice must be given to the Director, and approval obtained in advance of the time when the owner or operator expects to recompleate or abandon a well or to change plans. Within thirty (30) days after recompleation, change of plans, or remedial work, a detailed report of the work done and the results obtained shall be submitted on this form in duplicate for wells on Patented and Federal lands, and in triplicate for wells on State lands. In work that affects only rods, pumps or tubing or other routine work such as, but not limited to, cleaning out to previous total depth, no report is necessary.

Notice of Intention to Recomplete ☐Report of Remedial Work ☐Notice of Intention to Change Plans ☐Report of Recompleation ☐Notice of Intention to Abandon Well ☒Other ☐

(Check appropriate space)

LEASE NAME ZIEGLER WELL NO. A-3FIELD Yenter WILDCAT COUNTY LoganLOCATION NW/4 Section 2 Township 8 N Range 54 W Meridian 6PM
(Quarter Quarter)330 feet from North XXXX Section Line and 330 feet from West XXXX Section Line of Lot #9
N or S E or W

(DETAILS OF WORK)

This well completed in 1951 as a "J" sand producer but has been shut in since August 1960 when actual volume test was run and well was producing no oil and no water. Well had previously been perforated higher and two treatments increased production for a short period. As there is no other producing zone in this well it was proposed to plug and abandon or to sell for net salvage value to the highest bidder. The National Supply Company has purchased this well under the condition that they will salvage material and plug and abandon the well in accordance with the rules and regulations of the state Oil & Gas Conservation Commission. The well will be plugged by setting a rock and cement bridge above perforations, shoot off and pull the casing, fill hole with heavy mud with a 10 sax cement plug in bottom of surface casing and a 5 sax cement plug in top of surface casing, erect a dry hole marker, clean up and grade location. The National Supply Company will notify your Office when they are ready to start operations.

AJJ	
DVR	
WRS	
HHM	
JAM	
FJP	
LJD	<input checked="" type="checkbox"/>
FILE	

I/We hereby swear (or affirm) that the statements herein made are a full and correct report.

APPROVED:

MAR - 1 1961

Date

Director

Company British-American Oil Co Date Feb. 28, 1961Address Box 180; Denver 1, Colo Phone No. AC 2 9401By Norman W. Hoggan Title Dist Supt
(Signature)