

OFFICE OF STATE OIL INSPECTOR  
 SUNDRY NOTICES AND REPORTS OF WELLS  
 LOCATED ON PRIVATE LANDS

(Indicate nature of data by checking below)



- Notice of intention to drill \_\_\_\_\_
- Notice of intention to change plans \_\_\_\_\_
- Notice of date for test of water shut-off \_\_\_\_\_
- Report on result of test of water shut-off \_\_\_\_\_
- Notice of intention to re-drill or repair well \_\_\_\_\_
- Notice of intention to clean out well \_\_\_\_\_
- Statement of shooting \_\_\_\_\_
- Statement of perforating to lower G O R \_\_\_\_\_
- Notice to pull or otherwise alter casing \_\_\_\_\_
- Notice of intention to abandon well \_\_\_\_\_
- Report of work done on well since previous report \_\_\_\_\_
- ~~Subsequent report of production~~ \_\_\_\_\_

OCTOBER 25 1951

Following is a ~~(Notice of intention to do work)~~ (patented) described as follows:  
 (report of work done)

Colorado State Logan County Yenter Pool Field  
3 Ziegler A Sec. 2 NW/4 8 N 54 W  
 (Well No.) (Lease) (Sec. and 1/4 Sec.) (Twp.) (Range) (Meridian)

The well is located 330 ft. (N) of N LINE and 330 ft. (E) of W LINE  
S (S) (E)

The elevation above sea level is 4289 ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

August 7, 1951. Moved in Cable Tools and killed well with 100 Bbls. water into Casing. Squeezed off perforations 5145-5147' with 35 sax Cement. Drilled Cement to 5163' and perforated interval 5151-5157 with 3 Jet shots per ft. Followed with Hydrafrac job and no increase in production.

Perforated 5150-51' W/4 Jet shots. No fill up after 2 hours

"	5149-50'	"	"	"
"	5148-49'	"	"	"
"	5147-48'	"	"	"
"	5146-47'	"	"	"
"	5158-59'	"	"	"
"	5159-60'	"	"	"
"	5145-46'	"	Well filled up and flowed through Casing.	

September 5, 1951. Final Report- Well produced 61.5 BO & 3 BW 24 hrs. thru 14/64" Choke. G O R 5960 cu. ft. per Bbl.

Previous G O R 8620 cu. ft. per Bbl.

Approved: OCT 29 1951  
J. J. Zurek  
 State Oil Inspector  
 Director

Company BRITISH-AMERICAN OIL PROD. COMPANY  
 Address BOX 620, Casper, Wyoming.  
 By C. Wm. Evelyn Jr.  
 C. Wm. Evelyn Jr.  
 Title District Superintendent.

Submit reports of proposed work, for approval, on this form in Duplicate.