




COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS



(Indicate nature of data by checking below)

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report X

Following is a ~~(notice of intention to do work)~~ (report of work done) ~~(patented)~~ (unpatented) December 5, 1952 described as follows:

Colorado	Logan	Luft
State	County	Field
2	G. Morris	NE/4 20
(Well No.)	(Lease)	(Sec. and 1/4 Sec.)
		8N
		(Twp.)
		53W
		(Range)
		(Meridian)

The well is located 330 ft. (N) of N Line and 995 ft. (E) of W Line of NE/4 Section 20-8N-53W.
 (S) (W)

The elevation above sea level is 4183 ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

11-10-52 Spudded
 11-12-52 Ran and cemented 8 5/8" casing at 594 feet with 300 sacks
 11-18-52 Ran Schlumberger
 11-19-52 Cemented 5 1/2" casing at 4808 feet with 175 sacks and 4% gel.
 11-24-52 Drilled cement 4766 feet to 4808 feet.
 12-2-52 Connecting well up to flow.
 12-4-52 Flowed 677 barrels of oil, no water, 24 hours, GOR 433. Complete.

Schlumberger Tops:

Niobrara 4070
 Timpas 4293
 Bentonite 4717
 'Muddy' 4808

Approved: DEC 8 1952

Company Shell Oil Company

Address Denham Bldg., Denver, Colorado

By G. E. L. L. L.

Title Division Production Manager

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.