



SRC ENERGY

Operator: SRC Energy
Well Name: Aufrecht N 02-10
Legal: NWSE, Section 2, Township 5N, Range 67W
Location: Weld County, CO
API: 05-123-26505

Deepest Water Well
Within 1 Mile = 800'





Wellbore History

Spud Date: 2/15/2008
Surf Csg: 8.625", 24# @ 909' – 300 sx
Prod Csg: 4.5", 11.6# @ 7835' – 1050 sx
TOC: 1840' (CBL)
Perfs: CODL: 7213'-7233'

Actual P&A Procedure

Set CIBP @ 7138'
Set 43 sx on top of CIBP (567' plug)
Cut Casing @ 1009'
Pmp 361 sx @ 1064' to surface

Key

-  Existing Cement Coverage
-  CICR
-  Cement Pumped
-  CIBP

