

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:
401480257
Receive Date:
12/18/2017

Report taken by:
RICK ALLISON

Site Investigation and Remediation Workplan (Initial Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27.

This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Refer to Rules 340, 905, 906, 907, 908, 909, and 910

OPERATOR INFORMATON

Name of Operator: <u>PDC ENERGY INC</u>	Operator No: <u>69175</u>	Phone Numbers
Address: <u>1775 SHERMAN STREET - STE 3000</u>		Phone: <u>(303) 860-5800</u>
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80203</u>		Mobile: <u>()</u>
Contact Person: <u>Karen Olson</u>	Email: <u>Karen.Olson@pdce.com</u>	

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 10839 Initial Form 27 Document #: 401480257

PURPOSE INFORMATION

- 901.e. Sensitive Area Determination
- 909.c.(1), Rule 905: Pit or PW vessel closure
- 909.c.(2), Rule 906: Spill/Release Remediation
- 909.c.(3), Rule 907.e.: Land treatment of oily waste
- 909.c.(4), Rule 908.g.: Centralized E&P Waste Management Facility closure
- 909.c.(5), Rule 910.b.(4): Remediation of impacted ground water
- Rule 909.e.(2)A.: Notice completion of remediation in accordance with Rule 909.b.
- Rule 909.e.(2)B.: Closure of remediation project
- Rule 906.c.: Director request
- Other _____

SITE INFORMATION

N Multiple Facilites (in accordance with Rule 909.c.)

Facility Type: <u>LOCATION</u>	Facility ID: <u>331084</u>	API #: _____	County Name: <u>WELD</u>
Facility Name: <u>SETH-65N64W 19NWNE</u>	Latitude: <u>40.390095</u>	Longitude: <u>-104.590436</u>	
	** correct Lat/Long if needed: Latitude: <u>40.386229</u>	Longitude: <u>-104.583814</u>	
QtrQtr: <u>NWNE</u>	Sec: <u>19</u>	Twp: <u>5N</u>	Range: <u>64W</u> Meridian: <u>6</u> Sensitive Area? <u>Yes</u>

SITE CONDITIONS

General soil type - USCS Classifications SM Most Sensitive Adjacent Land Use Agriculture
 Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? Yes
 Is groundwater less than 20 feet below ground surface? Yes

Other Potential Receptors within 1/4 mile

An irrigation pond is located approximately 85 feet northeast of the location. Occupied housing is located approximately 295 feet south east of the location.

SITE INVESTIGATION PLAN

TYPE OF WASTE:

- | | | |
|--|--|--|
| <input checked="" type="checkbox"/> E&P Waste | <input type="checkbox"/> Other E&P Waste | <input type="checkbox"/> Non-E&P Waste |
| <input checked="" type="checkbox"/> Produced Water | <input type="checkbox"/> Workover Fluids | _____ |
| <input type="checkbox"/> Oil | <input type="checkbox"/> Tank Bottoms | |
| <input type="checkbox"/> Condensate | <input type="checkbox"/> Pigging Waste | |
| <input type="checkbox"/> Drilling Fluids | <input type="checkbox"/> Rig Wash | |
| <input type="checkbox"/> Drill Cuttings | <input type="checkbox"/> Spent Filters | |
| | <input type="checkbox"/> Pit Bottoms | |
| | <input type="checkbox"/> Other (as described by EPA) | _____ |

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
No	GROUNDWATER	Not defined.	Completion of Site Investigation Plan.
No	SOILS	Refer to Figure 1 and Table 1.	Completion of excavation activities.

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

Between October 3 and October 12, 2017, excavation oversight and confirmation sampling were conducted following the removal of the produced water vessel as the Seth 1, 5 production facility. Approximately 50 cubic yards of impacted material were removed and transported to the North Weld Waste Management Facility in Ault, Colorado for disposal under PDC waste manifests.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

As required by the COGCC Rule 905.B, one (1) soil sample (SS01) was collected at 4 feet below ground surface (bgs) from the excavation sidewall which exhibited the highest field screened volatile organic compound (VOC) concentration measured by a photoionization detector (PID). The soil sample was submitted to Summit Scientific Laboratories (Summit) in Golden, Colorado for analysis of benzene, toluene, ethylbenzene, total xylenes (BTEX), naphthalene, total petroleum hydrocarbons (TPH) - gasoline range organics (GRO) by USEPA Method 8260B, and TPH - diesel range organics (DRO) by USEPA Method 8015. Analytical results indicated that constituent concentrations were below the applicable COGCC Table 910-1 standards in the soil sample location. The excavation extent and soil sample locations are illustrated on Figure 1. Soil analytical results are summarized in Table 1.

Proposed Groundwater Sampling

Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Groundwater was encountered in the excavation at approximately 5 feet bgs. On October 12, 2017, one groundwater sample (GW01) was collected from the excavation following vacuum recovery events. The groundwater sample was submitted to Summit Scientific Laboratories for analysis of BTEX, by USEPA Method 8260B. Analytical results indicated that constituent concentrations were below applicable COGCC regulatory groundwater standards. The groundwater sample location is illustrated on Figure 1 and analytical results are summarized in Table 2.

Proposed Surface Water Sampling

Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

Additional alternative investigative actions described in attached Site Investigation Plan (summary):

Five (5) temporary monitoring wells will be installed via direct push drilling methods to confirm dissolved-phase hydrocarbon concentrations are below regulatory standards within and surrounding the former excavation extent. Proposed monitoring well locations are illustrated on Figure 2.

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 1
Number of soil samples exceeding 910-1 0
Was the areal and vertical extent of soil contamination delineated? Yes
Approximate areal extent (square feet) 100

NA / ND

ND Highest concentration of TPH (mg/kg) _____
NA Highest concentration of SAR _____
BTEX > 910-1 No
Vertical Extent > 910-1 (in feet) 4

Groundwater

Number of groundwater samples collected 1
Was extent of groundwater contaminated delineated? Yes
Depth to groundwater (below ground surface, in feet) 5'
Number of groundwater monitoring wells installed 0
Number of groundwater samples exceeding 910-1 0

ND Highest concentration of Benzene (µg/l) _____
ND Highest concentration of Toluene (µg/l) _____
ND Highest concentration of Ethylbenzene (µg/l) _____
ND Highest concentration of Xylene (µg/l) _____
NA Highest concentration of Methane (mg/l) _____

Surface Water

0 Number of surface water samples collected
0 Number of surface water samples exceeding 910-1
If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

Were impacts to adjacent property or offsite impacts identified?

Were background samples collected as part of this site investigation?

Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards) 50 Volume of liquid waste (barrels) 135

Is further site investigation required?

Temporary monitoring wells will be installed to confirm that dissolved-phase petroleum hydrocarbon impacts are not present on site. Proposed monitoring well locations are illustrated on Figure 2.

REMEDIAL ACTION PLAN

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Between October 3 and October 12, 2017, approximately 50 cubic yards of impacted material were removed and transported to the North Weld Waste Management Facility in Ault, Colorado for disposal under PDC waste manifests. As previously described, the confirmation soil sample collected from the final extent of the excavation indicated hydrocarbon impacts within the unsaturated interval were successfully removed by excavation activities.

REMEDICATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Five (5) temporary monitoring wells will be installed via direct push drilling methods in all cardinal directions of the former excavation extent. A remediation strategy may be selected for the site following the evaluation of groundwater analytical results.

Soil Remediation Summary

In Situ

- Bioremediation (or enhanced bioremediation)
- Chemical oxidation
- Air sparge / Soil vapor extraction
- Natural Attenuation
- Other _____

Ex Situ

- Excavate and offsite disposal
- If Yes: Estimated Volume (Cubic Yards) _____
- Name of Licensed Disposal Facility or COGCC Facility ID # _____
- Excavate and onsite remediation
- Land Treatment
- Bioremediation (or enhanced bioremediation)
- Chemical oxidation
- Other _____

Groundwater Remediation Summary

- Bioremediation (or enhanced bioremediation)
- Chemical oxidation
- Air sparge / Soil vapor extraction
- Natural Attenuation
- Other _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

Based on the analytical data collected during the initial site investigation, PDC proposes conducting one quarter of groundwater monitoring at the five (5) proposed monitoring wells. Should analytical results indicate BTEX concentrations are below COGCC Table 910-1 standards, PDC will request a No Further Action (NFA) determination for this site.

REMEDATION PROGRESS UPDATE

PERIODIC REPORTING

Frequency: Quarterly Semi-Annually Annually Other _____

Report Type: Groundwater Monitoring Land Treatment Progress Report O&M Report

Other _____

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

No beneficial use.

Volume of E&P Waste (solid) in cubic yards _____ 50

E&P waste (solid) description E&P contaminated soil.

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: North Weld Waste Management Facility

Volume of E&P Waste (liquid) in barrels _____ 135

E&P waste (liquid) description Groundwater

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: licensed disposal facility

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

The excavation area was backfilled, compacted, and re-graded to match pre-existing conditions. The produced water vessel and associated production infrastructure were decommissioned following excavation activities.

Is the described reclamation complete? Yes

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

Interim? Final?

Did the Surface Owner approve the seed mix? _____

If NO, does the seed mix comply with local soil conservation district recommendations? _____

IMPLEMENTATION SCHEDULE

PRIOR DATES

Date of Surface Owner notification/consultation, if required. _____

Actual Spill or Release date, if known. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). 10/03/2017

Date of commencement of Site Investigation. 10/03/2017

Date of completion of Site Investigation. _____

REMEDIAL ACTION DATES

Date of commencement of Remediation. 10/03/2017

Date of completion of Remediation. _____

SITE RECLAMATION DATES

Date of commencement of Reclamation. _____

Date of completion of Reclamation. _____

OPERATOR COMMENT

--

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Karen Olson

Title: Senior EHS Manager

Submit Date: 12/18/2017

Email: Karen.Olson@pdce.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: RICK ALLISON

Date: 01/04/2018

Remediation Project Number: 10839

COA Type

Description

--	--

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num

Name

401480257	FORM 27-INITIAL-SUBMITTED
401480433	ANALYTICAL RESULTS
401483729	SITE INVESTIGATION PLAN
401483732	SITE MAP

Total Attach: 4 Files

General Comments

User Group

Comment

Comment Date

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)