

FORM  
2A

Rev  
08/13

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401496849

(SUBMITTED)

Date Received:

Oil and Gas Location Assessment

☒ New Location ☐ Refile ☐ Amend Existing Location Location#: \_\_\_\_\_

This Oil and Gas Location Assessment is to be submitted to the COGCC for approval prior to any ground disturbance activity associated with oil and gas operations. Approval of this Oil and Gas Location Assessment will allow for the construction of the below specified Location; however, it does not supersede any land use rules applied by the local land use authority. Please see the COGCC website at <http://cogcc.state.co.us/> for all accompanying information pertinent this Oil and Gas Location Assessment.

Location ID:

Expiration Date:

☒ This location assessment is included as part of a permit application.

CONSULTATION

- ☐ This location is included in a Comprehensive Drilling Plan. CDP # \_\_\_\_\_
- ☐ This location is in a sensitive wildlife habitat area.
- ☐ This location is in a wildlife restricted surface occupancy area.
- ☐ This location includes a Rule 306.d.(1)A.ii. variance request.

Operator

Operator Number: 47120

Name: KERR MCGEE OIL & GAS ONSHORE LP

Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

Contact Information

Name: LISA SCHINDLER

Phone: (720) 929-3091

Fax: (720) 929-7267

email: LISA.SCHINDLER@ANADARKO.COM

RECLAMATION FINANCIAL ASSURANCE

☒ Plugging and Abandonment Bond Surety ID: 20010124

☐ Gas Facility Surety ID: \_\_\_\_\_

☐ Waste Management Surety ID: \_\_\_\_\_

LOCATION IDENTIFICATION

Name: ENGLISH FARMS

Number: 8-10HZ PAD

County: WELD

QuarterQuarter: SWSE Section: 8 Township: 1N Range: 65W Meridian: 6 Ground Elevation: 4945

Define a single point as a location reference for the facility location. When the location is to be used as a well site then the point shall be a well location.

Footage at surface: 315 feet FSL from North or South section line

2326 feet FEL from East or West section line

Latitude: 40.059617 Longitude: -104.686797

PDOP Reading: 1.6 Date of Measurement: 07/24/2017

Instrument Operator's Name: MARC RITT

## RELATED REMOTE LOCATIONS

(Enter as many Related Locations as necessary. Enter the Form 2A document # only if there is no established COGCC Location ID#)

**This proposed Oil and Gas Location is:**

**LOCATION ID #**

**FORM 2A DOC #**

Well Site is served by Production Facilities

401497471

## FACILITIES

Indicate the number of each type of oil and gas facility planned on location

Wells	6	Oil Tanks*		Condensate Tanks*		Water Tanks*		Buried Produced Water Vaults*	
Drilling Pits		Production Pits*		Special Purpose Pits		Multi-Well Pits*		Modular Large Volume Tanks	
Pump Jacks	6	Separators*		Injection Pumps*		Cavity Pumps*		Gas Compressors*	
Gas or Diesel Motors*		Electric Motors		Electric Generators*		Fuel Tanks*		LACT Unit*	
Dehydrator Units*		Vapor Recovery Unit*		VOC Combustor*		Flare*		Pigging Station*	

## OTHER FACILITIES\*

**Other Facility Type**

**Number**

FLOW LINE	18
TEMP 500 BBL TANKS W/ OPT ECDs	2

\*Those facilities indicated by an asterisk (\*) shall be used to determine the distance from the Production Facility to the nearest cultural feature on the Cultural Setbacks Tab.

Per Rule 303.b.(3)C, description of all oil, gas, and/or water pipelines:

Please see Comments section. Description of pipelines and flow lines does not fit in space provided.

Two 500 barrel skid-mounted frac tanks will be temporarily placed onsite for use of the pre-spud rig only. One tank will store water and the other will store water-based mud.

## CONSTRUCTION

Date planned to commence construction: 05/01/2018

Size of disturbed area during construction in acres: 7.06

Estimated date that interim reclamation will begin: 11/01/2018

Size of location after interim reclamation in acres: 0.60

Estimated post-construction ground elevation: 4945

## DRILLING PROGRAM

Will a closed loop system be used for drilling fluids: Yes

Is H<sub>2</sub>S anticipated? No

Will salt sections be encountered during drilling: No

Will salt based mud (>15,000 ppm Cl) be used? No

Will oil based drilling fluids be used? Yes

## DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE

Drilling Fluids Disposal Method: Commercial Disposal

Cutting Disposal: OFFSITE

Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

PLEASE SEE COMMENTS SECTION. DISPOSAL DESCRIPTION WILL NOT FIT IN THE SPACE PROVIDED

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: or Document Number:

Centralized E&P Waste Management Facility ID, if applicable: 149021

## SURFACE & MINERALS & RIGHT TO CONSTRUCT

Name: ENGLISH FARMS INC

Phone: 970-380-1163

Address: 14111 COUNTY ROAD 2

Fax: \_\_\_\_\_

Address: \_\_\_\_\_

Email: \_\_\_\_\_

City: WIGGINS State: CO Zip: 80654

Surface Owner: ☒ Fee ☐ State ☐ Federal ☐ Indian

Check all that apply. The Surface Owner: ☐ is the mineral owner

☐ is committed to an oil and Gas Lease

☐ has signed the Oil and Gas Lease

☐ is the applicant

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed from or produced to this Oil and Gas Location: Yes

The right to construct this Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: \_\_\_\_\_ Surface Surety ID: \_\_\_\_\_

Date of Rule 306 surface owner consultation 08/03/2017

## CURRENT AND FUTURE LAND USE

### Current Land Use (Check all that apply):

Crop Land: ☒ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☐ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): \_\_\_\_\_

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

### Future Land Use (Check all that apply):

Crop Land: ☒ Irrigated ☐ Dry land ☐ Improved Pasture ☐ Hay Meadow ☐ CRP

Non-Crop Land: ☐ Rangeland ☐ Timber ☐ Recreational ☐ Other (describe): \_\_\_\_\_

Subdivided: ☐ Industrial ☐ Commercial ☐ Residential

## CULTURAL DISTANCE INFORMATION

Provide the distance to the nearest cultural feature as measured from Wells or Production Facilities onsite.

	From WELL	From PRODUCTION FACILITY
Building:	523 Feet	Feet
Building Unit:	523 Feet	Feet
High Occupancy Building Unit:	5280 Feet	Feet
Designated Outside Activity Area:	5280 Feet	Feet
Public Road:	279 Feet	Feet
Above Ground Utility:	235 Feet	Feet
Railroad:	5280 Feet	Feet
Property Line:	280 Feet	Feet

### INSTRUCTIONS:

- All measurements shall be provided from center of nearest Well or edge of nearest Production Facility to nearest of each cultural feature as described in Rule 303.b.(3)A.  
- Enter 5280 for distance greater than 1 mile.  
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.  
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.  
- For measurement purposes only, Production Facilities should only include those items with an asterisk(\*) on the Facilities Tab.

## DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a:

- ☒ Buffer Zone  
☐ Exception Zone  
☐ Urban Mitigation Area

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: \_\_\_\_\_

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 12/01/2017

- Buffer Zone - as described in Rule 604.a.(2), within 1,000' of a Building Unit.  
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.  
- Urban Mitigation Area - as defined in 100-Series Rules.  
- Large UMA Facility - as defined in 100-Series Rules.

## FOR MULTI-WELL PADS AND PRODUCTION FACILITIES WITHIN DESIGNATED SETBACK LOCATIONS ONLY:

- ☐ Check this box if this Oil and Gas Location has or will have Production Facilities that serve multiple wells (on or offsite) and the Production Facilities are proposed to be located less than 1,000 feet from a Building Unit. *(Pursuant to Rule 604.c.(2)E.i., the operator must evaluate alternative locations for the Production Facilities that are farther from the Building Unit, and determine whether those alternative locations were technically feasible and economically practicable for the same proposed development.)*
- ☐ By checking this box, I certify that no alternative placements for the Production Facilities, farther from the nearest Building Unit, were available based on the analysis conducted pursuant to Rule 604.c.(2)E.i.

In the space below, explain rationale for siting the multi-well Production Facility(ies) that supports your Rule 604.c.(2)E.i determination. Attach documentation that supports your determination to this Form 2A.

## SOIL

List all soil map units that occur within the proposed location. attach the National Resource Conservation Service (NRCS) report showing the "Map Unit Description" report listing the soil typical vertical profile. This data is to be used when segregating topsoil.

The required information can be obtained from the NRCS web site at <http://soildatamart.nrcs.usda.org/> or from the COGCC web site GIS Online map page found at <http://colorado.gov/cogcc>. Instructions are provided within the COGCC web site help section.

NRCS Map Unit Name: 45 - Olney loamy sand, 3 to 5 percent slopes

NRCS Map Unit Name: 44 - Olney loamy sand, 1 to 3 percent slopes

NRCS Map Unit Name: \_\_\_\_\_

## PLANT COMMUNITY:

Complete this section only if any portion of the disturbed area of the location's current land use is on non-crop land.

Are noxious weeds present: Yes ☐ No ☐

Plant species from: ☐ NRCS or, ☐ field observation Date of observation: \_\_\_\_\_

List individual species:

Check all plant communities that exist in the disturbed area.

- ☐ Disturbed Grassland (Cactus, Yucca, Cheatgrass, Rye)
- ☐ Native Grassland (Bluestem, Grama, Wheatgrass, Buffalograss, Fescue, Oatgrass, Brome)
- ☐ Shrub Land (Mahogany, Oak, Sage, Serviceberry, Chokecherry)
- ☐ Plains Riparian (Cottonwood, Willow, Aspen, Maple, Poplar, Russian Olive, Tamarisk)
- ☐ Mountain Riparian (Cottonwood, Willow, Blue Spruce)
- ☐ Forest Land (Spruce, Fir, Ponderosa Pine, Lodgepole Pine, Juniper, Pinyon, Aspen)
- ☐ Wetlands Aquatic (Bullrush, Sedge, Cattail, Arrowhead)
- ☐ Alpine (above timberline)
- ☐ Other (describe): \_\_\_\_\_



## WATER RESOURCES

Is this a sensitive area: ☐ No ☒ Yes

Distance to nearest

downgradient surface water feature: 3450 Feet

water well: 513 Feet

Estimated depth to ground water at Oil and Gas Location 18 Feet

Basis for depth to groundwater and sensitive area determination:

Canal: 3450' SE (from well pad) Elev: 4944'

Pond: 55' W (from well pad) Elev: 4948'

Pond: 885' NW Elev: 4953'

Pond: 971' NW Elev: 4952'

Loc Elev: 4945'

NOTE: Ponds are man-made associated with former cattle feeding operation

Nearest water wells:

513' ESE, Permit 87167-, depth 55', Static Water Level 28', Elev 4955'

Sensitive Area Determination: SENSITIVE AREA, depth to groundwater less than 20'

Location is NOT in floodplain according to Weld County and FEMA

(SWL calc:  $(4945 - 4955) + 28 = 18$ )

Is the location in a riparian area: ☒ No ☐ Yes

Was an Army Corps of Engineers Section 404 permit filed ☒ No ☐ Yes If yes attach permit.

Is the location within a Rule 317B Surface Water Supply Area buffer No zone:

If the location is within a Rule 317B Surface Water Supply Area buffer have all public water supply systems within 15 miles been notified: \_\_\_\_\_

Is the Location within a Floodplain? ☒ No ☐ Yes Floodplain Data Sources Reviewed (check all that apply)

☒ Federal (FEMA)

☐ State

☒ County

☐ Local

☐ Other \_\_\_\_\_

## GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

## WILDLIFE

☐ This location is included in a Wildlife Mitigation Plan

☐ This location was subject to a pre-consultation meeting with CPW held on \_\_\_\_\_

### Operator Proposed Wildlife BMPs

No BMP

## DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 604.a.(1)A. Exception Zone (within 500' of a Building Unit) and is in an Urban Mitigation Area

- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

## RULE 502.b VARIANCE REQUEST

- ☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number \_\_\_\_\_

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

## OPERATOR COMMENTS AND SUBMITTAL

Comments

Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent possible, at which point they will either be land applied or taken to a licensed, commercial disposal site; the decision will be based upon laboratory analysis of fluids. KMG will reuse oil-based drilling fluids to the maximum extent possible, at which point they will be returned to the fluids manufacturer for reconditioning or disposal at a licensed, commercial disposal site.

Cuttings disposal: If the surface owner authorizes, and if it is feasible for this location at the time of drilling, water-based cuttings will be disposed of onsite using bioremediation/solidification product. If the surface owner does not authorize onsite disposal and/or it is not feasible for this location at the time of drilling, water-based cuttings will be disposed of using a Centralized E&P Waste Management facility or a private spread field. Oil-based cuttings will be disposed of offsite and at a licensed, commercial disposal site.

Flow Lines: 6 flow lines will flow to the production facility location. During production, flow direction in the flow lines is from the well head to the production facility. The size of flow lines is typically 2". Flow lines will be constructed from steel pipe, buried, and will equal the distance between the well heads and the tank battery, approximately 675'.

6 fuel gas supply lines will also be installed from the well head to the production facility. During operation flow direction in the supply lines will be from the production facility to the well head. The size of the supply lines is typically 1". Supply lines will be constructed from poly or steel pipe, buried, and will equal the distance between the well heads and the tank battery, approximately 675'.

Gas lift lines are also occasionally installed (one per well) from the well head to the production facility. During operation flow direction in the gas lift lines will be from the production facility to the well head. The size of the gas lift lines is typically 2". Gas lift lines will be constructed from steel pipe, buried, and will equal the distance between the well heads and the tank battery, approximately 675'.

CUSTODY TRANSFER: Gas custody transfer occurs at the custody transfer meter located on the proposed production facility location. Oil custody transfer occurs at the LACT Unit located on the proposed production facility location. Oil is transferred from the LACT Unit into a pipeline owned by Anadarko Wattenberg Oil Complex LLC.

I hereby certify that the statements made in this form are, to the best of my knowledge, true, correct and complete.

Signed: \_\_\_\_\_ Date: \_\_\_\_\_ Email: DJREGULATORY@ANADARKO.COM

Print Name: LISA SCHINDLER Title: SR REGULATORY ANALYST

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

## Conditions Of Approval

All representations, stipulations and conditions of approval stated in this Form 2A for this location shall constitute representations, stipulations and conditions of approval for any and all subsequent operations on the location unless this Form 2A is modified by Sundry Notice, Form 4 or an Amended Form 2A.

COA Type		Description
<b>Best Management Practices</b>		
No	BMP/COA Type	Description
1	Planning	604c.(2).E. Multi-Well Pads: In order to reduce surface impact, this application is for a 6-well pad.
2	Planning	604c.(2).Q. Guy Line Anchors: Guy line anchors will not be used. Base Beams will be used to stabilize the rig and removed after drilling.
3	Planning	604c.(2).R. Tank Specifications: Two 500 barrel skid-mounted frac tanks will be temporarily placed on-site for use of the pre-spud rig only. One tank will store water and the other will store water based mud.
4	Planning	604c.(2).S. Access Roads: KMG will utilize a lease access road from CR 10 for drilling, completions, and production operations, including maintenance equipment. The road will be properly constructed and maintained to accommodate for local emergency vehicle access.
5	Planning	604c.(2).V. Development From Existing Well Pads: Drilling from an existing well pad was not feasible for the development of the wells on this proposed oil and gas location; however, this well pad will be considered for future well locations.
6	Community Outreach and Notification	305.a.(2) A Notice of Intent to Conduct Operations was sent to each building unit owner within the Exception Zone or Buffer Zone Setback. Recipients did not contact KMG. As a part of planning this proposed location, Kerr-McGee held multi-disciplinary Surface Impact Planning Meetings regarding the impacts and mitigations associated with this proposed location. The toll-free hotline number and email for the Anadarko Colorado Response Line will be posted at the entrance to the lease access road for stakeholders during drilling and completion operations at this proposed location. Courtesy Notifications will be sent to impacted stakeholders prior to drilling operations and again prior to completions operations, providing contact information for the Anadarko Colorado Response Line and online resources.
7	Traffic control	604c.(2).D. Traffic Plan: Prior to the commencement of operations, the operator will obtain access and ROW permits per Weld County Code and implement COAs or traffic control plans as required.
8	Traffic control	KMG currently plans to use the water-on-demand system on this location which is a network of over 140 miles of underground pipeline which stretches the length of the 20 -mile x 30-mile field to source and transport water to completions crews. This system eliminates more than 2,000 truck trips per day, also reducing associated concerns of traffic, noise, emissions and dust.
9	General Housekeeping	604c.(2).O. Loadlines: All loadlines shall be bullplugged or capped.
10	General Housekeeping	604c.(2).P. Removal of Surface Trash: A commercial size trash bin for removing debris will be located on site. This bin will be for use by all parties affiliated with the operation. Upon completion of operations, the commercial trash bin will be removed from the location and disposed of in an appropriate manner.
11	Storm Water/Erosion Control	604c.(2).G. Berm Construction: Kerr-McGee will create tertiary containment by construction of a berm or diversion dike, site grading, or other comparable measures sufficient to further protect adjacent water features, including the man-made pond (associated with former cattle feeding operation) located 55' west of this proposed oil and gas location.
12	Storm Water/Erosion Control	604c.(2).W. Site-Specific Measures: KMG maintains a Storm Water Management Plan that assesses erosion control for every KMG operated location. This location will be added to this plan once construction begins. This site will be inspected every fourteen (14) days during construction activities, every twenty-eight (28) days after construction is completed, and after any major weather event.
13	Material Handling and Spill Prevention	606.A.d. Fire Prevention and Protection: KMG and its contractors will employ best management practices during the drilling and production of its wells and will comply with appropriate COGCC rules concerning fire prevention. Flammable liquids will not be stored within (fifty) 50' of the proposed wellheads. If storage of flammable liquid is to be conducted within (fifty) 50' of the wellhead, sufficient safety measures will be implemented.



14	Dust control	805.c. Dust: Water will be placed on dirt access roads to mitigate dust as needed. If feasible, magnesium chloride will also be used as needed on access roads to further abate dust.
15	Construction	604c.(2).M. Fencing Requirements: The completed wellsites will be surrounded with a fence and gate with adequate lock to restrict access to authorized personnel only. KMG personnel will monitor the wellsites regularly upon completion of the wells. Authorized representatives and/or KMG personnel shall be on-site during drilling and completion operations.
16	Noise mitigation	604c.(2).A. Noise: Sound surveys have been conducted on each rig type and are utilized to anticipate any additional effective noise mitigation once a drilling rig is determined. At a minimum, and pending a safety review after construction of the location, sound mitigation barriers (straw bales) will be placed along the south side of the pad location to dampen noise and minimize impact to the nearby residences and to Weld County Road 10 during drilling and completions. Should technological advancements allow for better noise mitigation at the time of drilling and completion operations on this location, Kerr-McGee will re-evaluate the most effective method at that time.
17	Odor mitigation	805b. Odors: KMG will comply with the provisions of 805b as deemed applicable. Additional BMPs for the ENGLISH FARMS 8-10HZ location are: 1) the storage of excess drilling fluid (e.g., fluid not being used in the active mud system) in closed, upright tanks; and 2) the use of an odor neutralizer in the active mud system.
18	Drilling/Completion Operations	604c.(2).B. Closed Loop Drilling System: KMG will use a closed loop or "pitless" system for drilling and fluid management and will not construct a reserve pit.
19	Drilling/Completion Operations	604c.(2).C. Green Completions: Temporary above ground polyethylene water pipelines will deliver water to location operations from larger trunk lines to reduce truck traffic and minimize air pollution. Pipeline infrastructure is in place prior to completions operations to ensure saleable gas, once hydrocarbons are cut, is sent directly to sales without flaring during flowback.
20	Drilling/Completion Operations	604c.(2).K. Pit Level Indicators: All storage tanks used for active drilling operations (used in lieu of pits) contain pit level monitors with Electronic Drilling Recorders (EDR). KMG uses EDRs with pit level monitor(s) and alarm(s) for production rigs. Basic level gauges are used on tanks utilized for the surface rig.
21	Drilling/Completion Operations	803. Lighting: To the extent practicable, site lighting shall be shielded and directed downward and inward toward operations to avoid glare on public roads and nearby Building Units.
22	Final Reclamation	604c.(2).T. Well Site Cleared: The wellsite will be cleared of all non-essential equipment within ninety (90) days after all wells associated with the pad have been plugged and abandoned.
23	Final Reclamation	604c.(2).U. Identification of Plugged and Abandoned Wells: Pursuant to rule 319.a.(5)., once the well has been plugged and abandoned, KMG will identify the location of the wellbore with a permanent monument that will detail the well name and date of plugging.

Total: 23 comment(s)

### Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401497440	WELL LOCATION PLAT
401497441	MULTI-WELL PLAN
401497443	LOCATION PICTURES
401497444	ACCESS ROAD MAP
401497445	NRCS MAP UNIT DESC
401497446	SURFACE AGRMT/SURETY
401497452	WASTE MANAGEMENT PLAN
401502418	LOCATION DRAWING
401502730	FACILITY LAYOUT DRAWING
401502740	HYDROLOGY MAP
401504067	PRE-APPLICATION NOTIFICATION CERTIFICATION

Total Attach: 11 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)

## **Public Comments**

No public comments were received on this application during the comment period.

