




**COLORADO OIL AND GAS CONSERVATION COMMISSION
SUNDRY NOTICES AND REPORTS OF WELLS**



OIL & GAS
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

333-16

Notice of intention to drill _____
 Notice of intention to change plans _____
 Notice of date for test of water shut-off _____
 Report on result of test of water shut-off _____
 Notice of intention to re-drill or repair well _____
 Notice of intention to clean out well _____
 Statement of shooting _____
 Statement of perforating _____
 Notice to pull or otherwise alter casing _____
 Notice of intention to abandon well _____
 Report of work done on well since previous report x _____

April 6 1953

Following is a ~~(notice of intention to do work)~~ (On-land)
 (report of work done) (patented) described as follows:

<u>Colorado</u>	<u>Logan</u>	<u>Luft</u>
State	County	Field
<u>4</u>	<u>G. Morris</u>	<u>NE/4 20</u>
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)
		<u>8N</u>
		(Twp.)
		<u>53W</u>
		(Range)
		<u>-</u>
		(Meridian)

The well is located 998 ft. ~~(NW)~~ (S) of N. Line and 330 ft. (E) of West Line of NE/4 Section 20-8N-53W. ~~(SE)~~

The elevation above sea level is 4185 ft.

Details of Plan of Work: (State names of and expected depths to objective sands: Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

12-24-52 Spudded.

12-26-52 Ran and cemented 8 5/8" casing at 595 feet with 300 sacks.

12-31-52 Ran Schlumberger.

1-2-52 Cemented 5 1/2" casing at 4829 feet with 100 sacks.

1-13-53 Drilled cement 4790-4829, cleaned out hole to 4839.

1-19-53 Running tubing.

1-21-53 Shut in for bottom hole pressure survey.

1-28-53 Waiting on Electrical System. Ran rods.

3-9-53 Installed Electrical System.

3-17-53 Pulled rods and pump. Change pump.

3-30-53 Pulled rods and tubing. Loaded hole with 65 barrels of oil.

4-1-53 Running tubing.

4-3-53 Pumping to stabilize

4-6-53 Pumped 192 barrels of oil, no water, in 24 hours. 50.5 MCFPD gas, GOR 290.

Complete.(over)

Approved: APR 8 1953

Company Shell Oil Company

Address Denham Building, Denver, Colorado

By W. H. Inabue

Title Division Production Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.