


COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS  
CONSERVATION COMMISSION

333-25



(Indicate nature of data by checking below)

- Notice of intention to drill \_\_\_\_\_
- Notice of intention to change plans \_\_\_\_\_
- Notice of date for test of water shut-off \_\_\_\_\_
- Report on result of test of water shut-off \_\_\_\_\_
- Notice of intention to re-drill or repair well \_\_\_\_\_
- Notice of intention to clean out well \_\_\_\_\_
- Statement of shooting \_\_\_\_\_
- Statement of perforating \_\_\_\_\_
- Notice to pull or otherwise alter casing \_\_\_\_\_
- Notice of intention to abandon well \_\_\_\_\_
- Report of work done on well since previous report  \_\_\_\_\_

Following is a ~~(notice of intention to do work)~~ May 15 1953  
(report of work done) ~~(on land)~~ (patented) described as follows:

Colorado	Logan	Luft
State	County	Field
8	G. Morris	NW/4 20
(Well No.)	(Lease)	(Sec. and $\frac{1}{4}$ Sec.)
		8N
		53W
		(Range) (Meridian)

The well is located 996 ft. ~~(S)~~ (N) of S Line and 330 ft. ~~(W)~~ (E) of E Line of NW/4 Section 20-T8N-R53W

The elevation above sea level is 4185 ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

- 4-23-53 Spudded.
- 4-26-53 Ran and cemented 8 5/8" casing at 590 feet with 280 sacks
- 4-30-53 Ran Schlumberger. Cemented 5 1/2" casing at 4838 feet with 100 sacks
- 5-4-53 Loaded hole with 70 bbls oil. Drilled shoe. Cleaned out to T.D.
- 5-5-53 Ran tubing.
- 5-8-53 Ran tubing and Baker tool, Stratafraced Muddy sandstone 4838-49 with 2000 gals. Jel X-500.
- 5-12-53 Installing pumping unit.
- 5-14-53 Pumped 56 bbls oil, 9 bbls acid wtr. in 24 hrs. 22.8 MCF gas. GOR 407  
Prod from Muddy 4838-49.

Complete

Schlumberger formation tops  
Niobrara 3980  
Timpas 4377  
Muddy 4836

Approved: MAY 19 1953

Company Shell Oil Company

J. J. Zarubek  
Director

Address 413 Denham Building

By W. H. Zarubek

Title Division Production Superintendent

Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.