

FORM
2

Rev
08/16

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401320174

APPLICATION FOR PERMIT TO:

☒ Drill ☐ Deepen ☐ Re-enter ☐ Recomplete and Operate

TYPE OF WELL OIL ☐ GAS ☒ COALBED ☐ OTHER _____

Refilling ☐

ZONE TYPE SINGLE ZONE ☒ MULTIPLE ZONES ☐ COMMINGLE ZONES ☐

Sidetrack ☐

Date Received:

06/30/2017

Well Name: QUARTER CIRCLE

Well Number: 24-7HZ

Name of Operator: KERR MCGEE OIL & GAS ONSHORE LP

COGCC Operator Number: 47120

Address: P O BOX 173779

City: DENVER

State: CO

Zip: 80217-3779

Contact Name: CRAIG RICHARDSON

Phone: (720)929-6092

Fax: (720)929-7093

Email: CRAIG.RICHARDSON@ANADARKO.COM

RECLAMATION FINANCIAL ASSURANCE

Plugging and Abandonment Bond Surety ID: 20010124

WELL LOCATION INFORMATION

QtrQtr: SESW Sec: 24 Twp: 1N Rng: 67W Meridian: 6

Latitude: 40.030335

Longitude: -104.841986

Footage at Surface: 344 Feet FNL/FSL FSL 1789 Feet FEL/FWL FWL

Field Name: WATTENBERG

Field Number: 90750

Ground Elevation: 4940

County: WELD

GPS Data:

Date of Measurement: 12/08/2016 PDOP Reading: 1.5 Instrument Operator's Name: ROB WILSON

If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FSL 1806 FWL 51 FNL 1837 FWL
Sec: 24 Twp: 1N Rng: 67W Sec: 13 Twp: 1N Rng: 67W

LOCATION SURFACE & MINERALS & RIGHT TO CONSTRUCT

Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Surface Owner is: ☐ is the mineral owner beneath the location.

(check all that apply) ☐ is committed to an Oil and Gas Lease.

☐ has signed the Oil and Gas Lease.

☐ is the applicant.

The Mineral Owner beneath this Oil and Gas Location is: ☒ Fee ☐ State ☐ Federal ☐ Indian

The Minerals beneath this Oil and Gas Location will be developed by this Well: Yes

The right to construct the Oil and Gas Location is granted by: Surface Use Agreement

Surface damage assurance if no agreement is in place: Surface Surety ID:

LEASE INFORMATION

Using standard QtrQtr, Sec, Twp, Rng format, describe one entire mineral lease that will be produced by this well (Describe lease beneath surface location if produced. Attach separate description page or map if necessary.)

Township 1 North, Range 67 West, 6th P.M.

Section 24: S/2S/2 except a tract described as: Comm. @ a point 1212' N. of SW/corner of 24, thence E 3132', thence S28°15'E 223', thence N83°15'E 371 ft., thence NO°45'E 272' to E/W centerline of said S/2 of 24, thence due W 3601' to W boundary line of said 24, thence due S 96' to p.o.b.

"Lessee agrees not to conduct any operations whatsoever on subject lands from April 1 through November 30 of any year this lease is in effect unless consent to do so is first acquired from Lessor."

Weld County, Colorado

Total Acres in Described Lease: 148 Described Mineral Lease is: ☒ Fee ☐ State ☐ Federal ☐ Indian

Federal or State Lease # _____

Distance from Completed Portion of Wellbore to Nearest Lease Line of described lease: 0 Feet

CULTURAL DISTANCE INFORMATION

Distance to nearest:

Building:	<u>882</u> Feet
Building Unit:	<u>882</u> Feet
High Occupancy Building Unit:	<u>5280</u> Feet
Designated Outside Activity Area:	<u>5280</u> Feet
Public Road:	<u>356</u> Feet
Above Ground Utility:	<u>341</u> Feet
Railroad:	<u>5280</u> Feet
Property Line:	<u>344</u> Feet

INSTRUCTIONS:

- All measurements shall be provided from center of the Proposed Well to nearest of each cultural feature as described in Rule 303.a.(5).
- Enter 5280 for distance greater than 1 mile.
- Building - nearest building of any type. If nearest Building is a Building Unit, enter same distance for both.
- Building Unit, High Occupancy Building Unit, and Designated Outside Activity Area - as defined in 100-Series Rules.

DESIGNATED SETBACK LOCATION INFORMATION

Check all that apply. This location is within a: ☒ Buffer Zone ☐ Exception Zone ☒ Urban Mitigation Area

- Buffer Zone – as described in Rule 604.a.(2), within 1,000' of a Building Unit
- Exception Zone - as described in Rule 604.a.(1), within 500' of a Building Unit.
- Urban Mitigation Area - as defined in 100-Series Rules.

Pre-application Notifications (required if location is within 1,000 feet of a building unit):

Date of Rule 305.a.(1) Urban Mitigation Area Notification to Local Government: 05/12/2017

Date of Rule 305.a.(2) Buffer Zone Notification to Building Unit Owners: 05/12/2017

SPACING and UNIT INFORMATION

Distance from completed portion of proposed wellbore to nearest completed portion of offset wellbore permitted or completed in the same formation: 124 Feet

Distance from Completed Portion of Wellbore to Nearest Unit Boundary 491 Feet (Enter 5280 for distance greater than 1 mile.)

Federal or State Unit Name (if appl): _____ Unit Number: _____

SPACING & FORMATIONS COMMENTS

PROPOSED SPACING UNIT:

01N67W SEC 24: E2W2

01N67W SEC 13: E2W

01N67W SEC 12: SESW

OBJECTIVE FORMATIONS

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		360	GWA

DRILLING PROGRAM

Proposed Total Measured Depth: 17397 Feet

Distance from the proposed wellbore to nearest existing or proposed wellbore belonging to another operator, including plugged wells:

Enter distance if less than or equal to 1,500 feet: 195 Feet ☐ No well belonging to another operator within 1,500 feet

Will a closed-loop drilling system be used? Yes

Is H₂S gas reasonably expected to be encountered during drilling operations at concentrations greater than or equal to 100 ppm? No (If Yes, attach an H₂S Drilling Operations Plan)

Will salt sections be encountered during drilling? No

Will salt based (>15,000 ppm Cl) drilling fluids be used? No

Will oil based drilling fluids be used? Yes

BOP Equipment Type: ☒ Annular Preventor ☒ Double Ram ☒ Rotating Head ☐ None

GROUNDWATER BASELINE SAMPLING AND MONITORING AND WATER WELL SAMPLING

Water well sampling required per Rule 318A

DRILLING WASTE MANAGEMENT PROGRAM

Drilling Fluids Disposal: OFFSITE Drilling Fluids Disposal Methods: Commercial Disposal

Cuttings Disposal: OFFSITE Cuttings Disposal Method: Commercial Disposal

Other Disposal Description:

Please see Comments section. Disposal description will not fit in space provided.

Beneficial reuse or land application plan submitted? Yes

Reuse Facility ID: _____ or Document Number: _____

CASING PROGRAM

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	16	42.1	0	40	30	40	0
SURF	13+1/2	9+5/8	36	0	1500	590	1500	0
1ST	7+7/8	5+1/2	17	0	17387	2060	17387	

☐ Conductor Casing is NOT planned

DESIGNATED SETBACK LOCATION EXCEPTIONS

Check all that apply:

- ☐ Rule 604.a.(1)A. Exception Zone (within 500' of Building Unit)
- ☐ Rule 604.b.(1)A. Exception Location (existing or approved Oil & Gas Location now within a Designated Setback as a result of Rule 604.a.)
- ☐ Rule 604.b.(1)B. Exception Location (existing or approved Oil & Gas Location is within a Designated Setback due to Building Unit construction after Location approval)
- ☐ Rule 604.b.(2) Exception Location (SUA or site-specific development plan executed on or before August 1, 2013)
- ☐ Rule 604.b.(3) Exception Location (Building Units constructed after August 1, 2013 within setback per an SUA or site-specific development plan)

GREATER WATTENBERG AREA LOCATION EXCEPTIONS

Check all that apply:

- ☒ Rule 318A.a. Exception Location (GWA Windows).
- ☒ Rule 318A.c. Exception Location (GWA Twinning).

RULE 502.b VARIANCE REQUEST

☐ Rule 502.b. Variance Request from COGCC Rule or Spacing Order Number _____

OTHER LOCATION EXCEPTIONS

Check all that apply:

☐ Rule 318.c. Exception Location from Rule or Spacing Order Number _____

☐ Rule 603.a.(2) Exception Location (Property Line Setback).

ALL exceptions and variances require attached Request Letter(s). Refer to applicable rule for additional required attachments (e.g. waivers, certifications, SUAs).

OPERATOR COMMENTS AND SUBMITTAL

Comments	<p>Please see the 318A.a. & 318.A.c. exception approval attached in the SUA memo on page 3, section 5.</p> <p>Drilling fluids disposal: KMG will reuse water-based drilling fluids to the maximum extent possible, at which point they will either be land applied or taken to a licensed, commercial disposal site; the decision will be based upon laboratory analysis of fluids. KMG will reuse oil-based drilling fluids to the maximum extent possible, at which point they will be returned to the fluids manufacturer for reconditioning or disposal at a licensed, commercial disposal site.</p> <p>Cuttings disposal: Water-based cuttings will be disposed of using a Centralized E&P Waste Management facility or a private spread field, depending on what is feasible at the time of drilling. Oil-based cuttings will be disposed of offsite and at a licensed, commercial disposal site.</p> <p>Pipelines: Buried pipelines will be utilized to gather the gas and oil product from the location (3 gas pipelines, 1 oil pipeline). Both gas and oil pipelines will be constructed from steel of suitable wall thickness and material grade to meet the respective gathering systems design pressure. Gas pipelines will range in diameter from 4" to 20"; oil pipelines from 4" to 12". Capacity of pipelines will vary based on diameter. Pipelines will begin at the location and terminate at larger trunk lines in the area. Temporary above ground polyethylene water pipelines (diameter 10" – 12" with a 60 BPM capacity) will deliver water to location operations from larger trunk lines.</p> <p>33 flow lines will flow to the production facility location. During production, flow direction in the flow lines is from the well head to the production facility. The size of flow lines is typically 2". Flow lines will be constructed from steel pipe, buried, and will equal the distance between the well heads and the tank battery, approximately 1000'.</p> <p>33 fuel gas supply lines will also be installed from the well head to the production facility. During operation flow direction in the supply lines will be from the production facility to the well head. The size of the supply lines is typically 1". Supply lines will be constructed from poly or steel pipe, buried, and will equal the distance between the well heads and the tank battery, approximately 1000'.</p> <p>Gas lift lines are also occasionally installed (one per well) from the well head to the production facility. During operation flow direction in the gas lift lines will be from the production facility to the well head. The size of the gas lift lines is typically 2". Gas lift lines will be constructed from steel pipe, buried, and will equal the distance between the well heads and the tank battery, approximately 1000'.</p> <p>This proposed well will have a treated interval less than one hundred fifty (150) feet from the treated interval of another well and is subject to COGCC Rule 317.r.</p> <p>The following well(s) belong to Kerr-McGee and will have treated intervals within one hundred fifty (150) feet of this proposed well: RIVERBEND 6-13 2A KIEFER GEORGE W UNIT B - This well is P&A'd</p> <p>The following well(s) are not within 150' of KMG's proposed well, however may appear to be less than 150' in 2D view: RIVERBEND 3-13 RIVERBEND 36-12</p>
----------	--

This application is in a Comprehensive Drilling Plan No CDP #: _____

Location ID: _____

Is this application being submitted with an Oil and Gas Location Assessment application? Yes

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CRAIG RICHARDSON

Title: REGULATORY ANALYST II Date: 6/30/2017 Email: DJREGULATORY@ANDARKO

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____



Director of COGCC

Date: 1/11/2018

Expiration Date: 01/10/2020

API NUMBER

05 123 46268 00

Conditions Of Approval

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COA Type

Description

	This Permit to Drill is approved subject to all the BMPs and COAs on the most recently approved Form 2A and any subsequently approved Form 4 for the Oil and Gas Location. The most recently approved Form 2A and any subsequent Form 4s containing applicable COAs for this location shall be posted onsite during construction, drilling, and completions operations.
	Operator acknowledges the proximity of the listed wells. Operator agrees to: provide mitigation option 1 or 2 (per the DJ Basin Horizontal Offset Policy) to mitigate the situation, ensure all applicable documentation is submitted based on the selected mitigation option chosen, and submit a Form 42 ("OFFSET MITIGATION COMPLETED") stating that appropriate mitigation occurred and that it has been completed, prior to the hydraulic stimulation of this well. 05-123-19890, HSR-MYRNA 15-12A 05-123-11008, KIEFER POOLING UNIT 2 05-123-11181, HARRY S CHIKUMA GU B-TRUE 1
	1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU (spud notice) for the first well activity with a rig on the pad and provide 48 hour spud notice via Form 42 for all subsequent wells drilled on the pad. 2) Comply with Rule 317.j. and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log. 3) Oil-based drilling fluid is to be used only after all fresh water aquifers are covered.
	Bradenhead tests shall be performed according to the following schedule and the Form 17 submitted within 10 days of each test: 1) Within 60 days of rig release and prior to stimulation and 2) If a delayed completion, 6 months after rig release and prior to stimulation. 3) Within 30 days after first production, as reported on Form 5A.

Best Management Practices

No	BMP/COA Type	Description
1	Drilling/Completion Operations	604c.(2).B. Closed Loop Drilling System: KMG will use a closed loop or "pitless" system for drilling and fluid management and will not construct a reserve pit.
2	Drilling/Completion Operations	604c.(2).C. Green Completions: Temporary above ground polyethylene water pipelines will deliver water to location operations from larger trunk lines to reduce truck traffic and minimize air pollution. Pipeline infrastructure is in place prior to completions operations to ensure saleable gas, once hydrocarbons are cut, is sent directly to sales without flaring during flowback. Environmental Control Devices or Volatile Organic Compound (VOC) Combustors will be used to control working and breathing vapor losses for oil and water tanks.
3	Drilling/Completion Operations	604c.(2).H. BOPE: Our rigs at a minimum will have a double ram with blind and pipe ram and annular preventer.
4	Drilling/Completion Operations	604c.(2).I. BOPE Testing for Drilling Operations: BOPEs will be tested upon rig-up and, at a minimum, every 30 days.
5	Drilling/Completion Operations	604c.(2).J. BOPE for Well Servicing Operations: Blowout prevention equipment will be used on any servicing operations associated with this well. Backup stabbing valves will be used during any future servicing operations during reverse circulation. Valves shall be pressure tested before each well servicing operation using low-pressure air and high-pressure fluid.
6	Drilling/Completion Operations	604c.(2).K. Pit Level Indicators: All storage tanks used for active drilling operations (used in lieu of pits) contain pit level monitors with Electronic Drilling Recorders (EDR). KMG uses EDRs with pit level monitor(s) and alarm(s) for production rigs. Basic level gauges are used on tanks utilized for the surface rig.
7	Drilling/Completion Operations	604c.(2).L. Drill Stem Tests: No drill stem tests are planned and none will be performed without prior approval from the Director.
8	Drilling/Completion Operations	605.c.(1) Special Equipment: Wells will be equipped with automatic control valves and will continuously be monitored by the Integrated Operations Center (IOC) such that if a sudden change in pressure is detected the well will be shut in and fail safe.
9	Drilling/Completion Operations	803. Lighting: To the extent practicable, site lighting shall be shielded and directed downward and inward toward operations to avoid glare on public roads and nearby Building Units.
10	Drilling/Completion Operations	Kerr-McGee acknowledges and will comply with the COGCC Policy for Bradenhead Monitoring during Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
11	Drilling/Completion Operations	Anti-Collision: Kerr-McGee will perform an anti-collision evaluation of all active (producing, shut in, or temporarily abandoned) offset wellbores that have the potential of being within one hundred fifty (150) feet of a proposed well prior to drilling operations for the proposed well. Notice shall be given to all offset operators within one hundred fifty (150) feet prior to drilling.
12	Drilling/Completion Operations	317.p Logging Program: One of the first wells drilled on the pad will be logged with Open Hole Resistivity Log and Gamma Ray Log from the kick-off point into the surface casing. All wells on the pad will have a cement bond log with gamma-ray run on production casing (or on intermediate casing if production liner is run) into the surface casing. The horizontal portion of every well will be logged with a measured-while-drilling gamma-ray log. The form 5, Completion Report, for each well on the pad will list all logs run and have those logs attached. The Form 5 for a well without open-hole logs shall clearly state "No open-hole logs were run" and shall clearly identify (by API#, well name & number) the well in which open-hole logs were run.

Total: 12 comment(s)

Applicable Policies and Notices to Operators

Policy
Notice Concerning Operating Requirements for Wildlife Protection. http://cogcc.state.co.us/documents/reg/Policies/Wildlife_Notice.pdf
Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area. http://cogcc.state.co.us/documents/reg/Policies/PolicyGwaBradenheadMonitoringFinal.pdf

Attachment Check List

<u>Att Doc Num</u>	<u>Name</u>
401320174	FORM 2 SUBMITTED
401326792	WELL LOCATION PLAT
401326796	DEVIATED DRILLING PLAN
401326797	DIRECTIONAL DATA
401326809	EXCEPTION LOC REQUEST
401326811	LEASE MAP
401326813	SURFACE AGRMT/SURETY
401328313	PROPOSED SPACING UNIT
401341073	OffsetWellEvaluations Data
401511550	OFFSET WELL EVALUATION

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed.	01/10/2018
Permit	With operators concurrence changed distance to nearest unit boundary. Permitting Review Complete.	01/04/2018
Permit	Open Hole Logging BMP submitted by operator. Please see the 318A.a. & 318.A.c. exception approval attached in the SUA memo on page 3, section 5. ON HOLD: requesting corrected distance to nearest unit boundary.	01/02/2018
Engineer	317.r is not about the treated interval, if any portion of a wellbore has the potential of being within 150' of another well then it is subject to 317.r for anti-collision prevention.	12/11/2017
LGD	The City has no concerns on this project.	07/21/2017
Permit	"Offset Wells Evaluation" tab: the "Operator's Wellbore Integrity Email" had been left blank as well as on the "Offset Well Evaluation" attachment. With Operator's permission, added in the following email in for both: JOHN.COOKE@ANADARKO.COM Passed Completeness.	07/13/2017

Total: 6 comment(s)