

**FORM  
INSP**

Rev  
X/15

**State of Colorado  
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203  
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

01/17/2018

Submitted Date:

01/17/2018

Document Number:

688600220

**FIELD INSPECTION FORM**

Loc ID 428669 Inspector Name: BURGER, CRAIG On-Site Inspection  2A Doc Num: \_\_\_\_\_

**Status Summary:**

- THIS IS A FOLLOW UP INSPECTION
- FOLLOW UP INSPECTION REQUIRED
- NO FOLLOW UP INSPECTION REQUIRED

**Operator Information:**

OGCC Operator Number: 1  
Name of Operator: UNKNOWN  
Address: \_\_\_\_\_  
City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_

**Findings:**

- 2 Number of Comments
- 1 Number of Corrective Actions
- Corrective Action Response Requested

**Contact Information:**

Contact Name	Phone	Email	Comment
Andrews, Dave		david.andrews@state.co.us	

**Inspected Facilities:**

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
425793	WELL	TA	10/12/2011	LO	077-40017	Lloyd and Lowell 1	TA

**General Comment:**

Orphan well plugging project. Contractor is RACS.

**Inspected Facilities**

Facility ID: 425793 Type: WELL API Number: 077-40017 Status: TA Insp. Status: TA

**Workover**

Comment: 8 am on location. Slickline tagged at 83', got 60 foot plug from 40 sacks.  
Well static, gas not detected with 4 gas meter.  
RIH tubing to 55' and circulated.  
Pumped 60 sacks cement with returns to surface.  
Excavated around casing, pulled conductor pipe, rig down and demobilize.

Corrective Action: **Plug and abandon**

Date: 01/31/2018