

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

401303811

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 96850

Contact Name: KELLYE GARCIA

Name of Operator: TEP ROCKY MOUNTAIN LLC

Phone: (832) 726-1159

Address: PO BOX 370

Fax:

City: PARACHUTE State: CO Zip: 81635

API Number 05-045-23351-00

County: GARFIELD

Well Name: Chevron

Well Number: TR 324-21-597

Location: QtrQtr: SESW Section: 21 Township: 5S Range: 97W Meridian: 6

Footage at surface: Distance: 718 feet Direction: FSL Distance: 1874 feet Direction: FWL

As Drilled Latitude: 39.593881 As Drilled Longitude: -108.285782

## GPS Data:

Date of Measurement: 12/14/2016 PDOP Reading: 1.7 GPS Instrument Operator's Name: J. KIRKPATRICK

\*\* If directional footage at Top of Prod. Zone Dist.: 1241 feet. Direction: FSL Dist.: 1330 feet. Direction: FEL

Sec: 21 Twp: 5S Rng: 97W

\*\* If directional footage at Bottom Hole Dist.: 1203 feet. Direction: FSL Dist.: 1374 feet. Direction: FEL

Sec: 21 Twp: 5S Rng: 97W

Field Name: TRAIL RIDGE

Field Number: 83825

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 01/13/2017 Date TD: 03/10/2017 Date Casing Set or D&amp;A: 03/11/2017

Rig Release Date: 04/19/2017 Per Rule 308A.b.

## Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 9871 TVD\*\* 9407 Plug Back Total Depth MD 9826 TVD\*\* 9362

Elevations GR 8292 KB 8316 Digital Copies of ALL Logs must be Attached per Rule 308A ☒

## List Electric Logs Run:

CBL/PULSED NEUTRON LOG/TRIPLE COMBO IN 045-23339

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	47.44	0	63	105	0	63	VISU
SURF	14+3/4	9+5/8	36	0	2,714	2,129	0	2,714	VISU
1ST	8+3/4	4+1/2	11.6	0	9,865	1,325	3,200	9,865	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH	2,641				
WASATCH G	4,549				
MESAVERDE	5,969				Mesaverde top is the Ohio Creek Top.
OHIO CREEK	5,969				The Ohio Creek Top is the Mesaverde Top.
WILLIAMS FORK	6,195				
CAMEO	8,711				
ROLLINS	9,060				
COZZETTE	9,242				
CORCORAN	9,470				
SEGO	9,650				

Comment:

The GPS date of measurement is actual data of the existing well conductor location prior to spud date.

No Open Hole Logs were run on this well. Triple Combination Logs were run on TR 313-21-597 (045-23339).

No MUD logs were run on this well.

The surface string cement total includes 1015 sacks of top out cement totaling to 2129 sacks of cement.

PBTD matches CBL per Craig Burger.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: KELLYE GARCIA

Title: LAND TECHNICIAN

Date: \_\_\_\_\_

Email: KGARCIA@TERRAEP.COM

### Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401521230	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401332942	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401303820	LAS-CBL 1ST RUN	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401303822	PDF-CBL 1ST RUN	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401332943	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401521132	LAS-PULSED NEUTRON	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401521141	PDF-PULSED NEUTRON	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)