



Daily Completion and Workover

Well Name: STATE AF 01

Report Date: 1/9/2018, Report # 9.0

API 0512305368	Surface Legal Location	Field Name	License #	State/Province COLORADO	Well Configuration Type
Original KB Elevation (ft)	KB-Tubing Head Distance (ft)	Spud Date Production	Rig Release Date	PBTD (All) (ftKB)	Total Depth All (TVD) (ftKB)

Jobs					
Job Category WORKOVER	Primary Job Type P&A	Secondary Job Type Drilling - re-entry	Target Formation	Start Date 12/28/2017	End Date

Objective

Rigs					
Contractor BRIGADE ENERGY SERVICES	Rig #/Crw Conventional	Rig Type	Start Date 12/28/2017	RR Date	

AFE Number	Total AFE + Supp Amount (Cost)	[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]
------------	--------------------------------	------------	------------	------------	------------

Daily Readings			
Weather	Temperature (°F)	Road Condition	Rig Time (hr)

Daily Ops Summary

Operations Summary
 JSA SAFETY MEETING, 0 PSI ON WELL TIH AND HARD TAG ON TOC @ 2621' W/ 80 JNTS 2-7/8" TBG= 100' PLUG
 TOOH LD TBG 67 JNTS LEAVING 13 JNTS IN HOLE AND EOT @ 427' PER FORM 6, PUMP 7 BBL TO LOAD HOLE
 MIRU O-TEX CEMENT AND LRP CLEAN WATER TRUCK, TEST WATER FOR CEMENT JOB, JSA SAFETY MEETING
 FILL LINES AND P/T TO 2000 PSI, PUMP SHOE PLUG AS FOLLOWS:
 ESTABLISH CIRCULATION 30 BBL AND PUMP 80 BBL/16.3 BBL 15.8# G-NEAT CEMENT FROM 427' - 240' +/-, DISP 0.5 BBL
 TOOH LD TBG TO TRAILER, SECURED WELL AND WASH UP TO CT, SDFN

Tangible/Intangible Costs			
Intangible/Tangible	[REDACTED]	[REDACTED]	[REDACTED]
[REDACTED]	[REDACTED]	[REDACTED]	[REDACTED]