

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401528260

Receive Date:

01/29/2018

Report taken by:

PETER GINTAUTAS

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Refer to Rules 340, 905, 906, 907, 908, 909, and 910

OPERATOR INFORMATION

Name of Operator: NOBLE ENERGY INC	Operator No: 100322	Phone Numbers
Address: 1001 NOBLE ENERGY WAY		Phone: (970) 3045329
City: HOUSTON State: TX Zip: 77070		Mobile: ()
Contact Person: Jacob Evans	Email: jacob.evans@nblenergy.com	

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 8952 Initial Form 27 Document #: 2314239

PURPOSE INFORMATION

- | | |
|--|--|
| <input checked="" type="checkbox"/> 901.e. Sensitive Area Determination | <input checked="" type="checkbox"/> 909.c.(5), Rule 910.b.(4): Remediation of impacted ground water |
| <input type="checkbox"/> 909.c.(1), Rule 905: Pit or PW vessel closure | <input type="checkbox"/> Rule 909.e.(2)A.: Notice completion of remediation in accordance with Rule 909.b. |
| <input checked="" type="checkbox"/> 909.c.(2), Rule 906: Spill/Release Remediation | <input type="checkbox"/> Rule 909.e.(2)B.: Closure of remediation project |
| <input type="checkbox"/> 909.c.(3), Rule 907.e.: Land treatment of oily waste | <input type="checkbox"/> Rule 906.c.: Director request |
| <input type="checkbox"/> 909.c.(4), Rule 908.g.: Centralized E&P Waste Management Facility closure | <input type="checkbox"/> Other |

SITE INFORMATION

N Multiple Facilities (in accordance with Rule 909.c.)

Facility Type: SPILL OR RELEASE	Facility ID: 437104	API #:	County Name: WELD
Facility Name: SPILL/RELEASE POINT	Latitude: 40.289953	Longitude: -104.755675	
** correct Lat/Long if needed: Latitude:		Longitude:	
QtrQtr: NENE	Sec: 27	Twp: 4N	Range: 66W Meridian: 6 Sensitive Area? Yes

SITE CONDITIONS

General soil type - USCS Classifications SP Most Sensitive Adjacent Land Use Crop Land

Is domestic water well within 1/4 mile? Yes Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? Yes

Other Potential Receptors within 1/4 mile

Irrigation well 0.13 mi south-southwest, domestic water wells 0.06 mi NE, 0.15 mi NE, & 0.22 mi NE

SITE INVESTIGATION PLAN

TYPE OF WASTE:

☒ E&P Waste

☐ Other E&P Waste

☐ Non-E&P Waste

☒ Produced Water

☐ Workover Fluids

☐ Oil

☐ Tank Bottoms

☐ Condensate

☐ Pigging Waste

☐ Drilling Fluids

☐ Rig Wash

☐ Drill Cuttings

☐ Spent Filters

☐ Pit Bottoms

☐ Other (as described by EPA)

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	GROUNDWATER	180' X 180'	Laboratory Analytical
Yes	SOILS	50' N-S x 70' E-W x15' total depth	Excavation soil sample results

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

A historical release was discovered during removal of a water vault. The production equipment has been shut in. Please refer to Form 19 submitted May 6, 2014 (document #400611726).

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Twenty soil samples were collected and analyzted for TPH-DRO, TPH-GRO, BTEX, and Naphthalene by a certified laboratory.

Proposed Groundwater Sampling

☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Ten groundwater samples were collected and analyzed for BTEX by a certified laboratory.

Proposed Surface Water Sampling

☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

☐ Additional alternative investigative actions described in attached Site Investigation Plan (summary):

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 20

Number of soil samples exceeding 910-1 5

Was the areal and vertical extent of soil contamination delineated? Yes

Approximate areal extent (square feet) 3500

NA / ND

-- Highest concentration of TPH (mg/kg) 5682

NA Highest concentration of SAR

BTEX > 910-1 Yes

Vertical Extent > 910-1 (in feet) 15

Groundwater

Number of groundwater samples collected 10

Was extent of groundwater contaminated delineated? Yes

Depth to groundwater (below ground surface, in feet) 7'

Number of groundwater monitoring wells installed 9

Number of groundwater samples exceeding 910-1 5

-- Highest concentration of Benzene (µg/l) 17800

-- Highest concentration of Toluene (µg/l) 6740

-- Highest concentration of Ethylbenzene (µg/l) 745

-- Highest concentration of Xylene (µg/l) 11500

NA Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected

Number of surface water samples exceeding 910-1

If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☐ Were background samples collected as part of this site investigation?

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards)

Volume of liquid waste (barrels)

☐ Is further site investigation required?

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No _____

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Approximately 2,530 cubic yards of impacted soil was excavated. Confirmation soil samples indicate that impacted soil in exceedance of the applicable Colorado Oil and Gas Conservation Commission (COGCC) Table 910-1 standards was removed via excavation activities.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

Residual soil and groundwater impacts are being treated using air sparge/soil vapor extraction technology.

Soil Remediation Summary

☒ **In Situ**

No _____ Bioremediation (or enhanced bioremediation)

No _____ Chemical oxidation

Yes _____ Air sparge / Soil vapor extraction

Yes _____ Natural Attenuation

No _____ Other _____

☒ **Ex Situ**

Yes _____ Excavate and offsite disposal

If Yes: Estimated Volume (Cubic Yards) _____ 2530

Name of Licensed Disposal Facility or COGCC Facility ID # _____

No _____ Excavate and onsite remediation

_____ Land Treatment

_____ Bioremediation (or enhanced bioremediation)

_____ Chemical oxidation

_____ Other _____

Groundwater Remediation Summary

No _____ Bioremediation (or enhanced bioremediation)

No _____ Chemical oxidation

Yes _____ Air sparge / Soil vapor extraction

Yes _____ Natural Attenuation

No _____ Other _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

Monitoring wells MW01, MW05, MW08, MW09, and MW13 will be sampled on a quarterly basis to monitor dissolved phase BTEX and ensure the plume is stable and decreasing.

REMEDATION PROGRESS UPDATE

PERIODIC REPORTING

Frequency: ☐ Quarterly ☐ Semi-Annually ☒ Annually ☐ Other _____

Report Type: ☒ Groundwater Monitoring ☐ Land Treatment Progress Report ☐ O&M Report
☐ Other _____

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

No beneficial reuse

Volume of E&P Waste (solid) in cubic yards 2530

E&P waste (solid) description Impacted soil above COGCC Table 910-1 standards

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: Buffalo Ridge Landfill

Volume of E&P Waste (liquid) in barrels 0

E&P waste (liquid) description _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: _____

REMEDATION COMPLETION REPORT

REMEDATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No

Do all soils meet Table 910-1 standards? No

Does the previous reply indicate consideration of background concentrations? _____

Are the only residual soil impacts pH, SAR, or EC at depths greater than 3 feet below ground surface? No

Does Groundwater meet Table 910-1 standards? No

Is additional groundwater monitoring to be conducted? Yes

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

The excavation was backfilled with clean fill to re-establish the pre-existing grade. Reclamation will be compliant with the COGCC Reclamation Rule 1004-Final Reclamation of Well Sites and Associated Production Facilities.

Is the described reclamation complete? Yes

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim? ☒ Final?

Did the Surface Owner approve the seed mix? _____

If NO, does the seed mix comply with local soil conservation district recommendations? _____

IMPLEMENTATION SCHEDULE

PRIOR DATES

Date of Surface Owner notification/consultation, if required. _____

Actual Spill or Release date, if known. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). _____

Date of commencement of Site Investigation. 05/22/2014

Date of completion of Site Investigation. _____

REMEDIAL ACTION DATES

Date of commencement of Remediation. 04/29/2014

Date of completion of Remediation. _____

SITE RECLAMATION DATES

Date of commencement of Reclamation. _____

Date of completion of Reclamation. _____

OPERATOR COMMENT

Lorenz UPRR 42-27

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Jacob Evans

Title: Environmental Coordinator

Submit Date: 01/29/2018

Email: jacob.evans@nblenergy.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: PETER GINTAUTAS

Date: 01/29/2018

Remediation Project Number: 8952

COA Type

Description

	Submit reports of site investigation and progress of remediation including results of sampling and analysis on an annual basis or more often until remediation is closed.
--	---

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num

Name

401528260	FORM 27-SUPPLEMENTAL-SUBMITTED
401528266	MONITORING REPORT

Total Attach: 2 Files

General Comments

User Group

Comment

Comment Date

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)