



SRC ENERGY

Re-Enter to Re-Plug Wellbore Diagram

Operator: Cache Exploration Inc

Operator #: 12835

Well Name: Barney 3

Location: Weld, CO

API: 05-123-15755

Legal: SESW 23-6N-66W

Current

Proposed

Deepest Water Well (1 mile): 80'

Well History

Spud Date: 05/08/1992

Perfs: Codell: 7168' - 7178'

Bradenhead History

Date of last test: N/A

Bradenhead Pressure: N/A

Previous Plugging Procedure

Set CIBP @ 7108' w/ 2 sx on top

Cut 4.5" casing @ 5963'

Set 40 sx at SC Shoe (129' plug)

Set 10 sx @ surface (32' plug)

Proposed Plugging Procedure

Mill cement in surface casing (btm \approx 365')

Wash to 6013'

Set 184 sx @ 6013' (500' plug)

WOC 4 hours and tag plug

Set 184 sx @ 4000' (500' plug)

WOC 4 hours and tag plug

Set 92 sx @ 2250' (250' plug)

WOC 4 hours and tag plug

Set 228 sx @ 600' to surface

WOC 4 hours and tag plug

Formations

Codell (Top) 7163'

Legend



Existing Cement



Cement Pumped



CIBP



CICR

