

FORM
5A

Rev
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401543503

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850
2. Name of Operator: TEP ROCKY MOUNTAIN LLC
3. Address: PO BOX 370
City: PARACHUTE State: CO Zip: 81635
4. Contact Name: Kellye Garcia
Phone: (832) 726-1159
Fax:
Email: kgarcia@terraep.com

5. API Number 05-045-23454-00
6. County: GARFIELD
7. Well Name: WARE
Well Number: SR 13-12
8. Location: QtrQtr: NESW Section: 12 Township: 7S Range: 94W Meridian: 6
9. Field Name: RULISON Field Code: 75400

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 01/02/2018 End Date: 01/07/2018 Date of First Production this formation: 01/25/2018

Perforations Top: 7650 Bottom: 9675 No. Holes: 240 Hole size: 35/100

Provide a brief summary of the formation treatment: Open Hole: ☐

52137 bbls of slickwater; 994500 100/Mesh; 1338 gals of biocide

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 52169 Max pressure during treatment (psi): 8121

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.71

Total acid used in treatment (bbl): Number of staged intervals: 10

Recycled water used in treatment (bbl): 52137 Flowback volume recovered (bbl): 20455

Fresh water used in treatment (bbl): Disposition method for flowback: RECYCLE

Total proppant used (lbs): 994500 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 01/25/2018 Hours: 24 Bbl oil: 0 Mcf Gas: 1223 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 1223 Bbl H2O: 0 GOR: 0

Test Method: FLOWING Casing PSI: 2150 Tubing PSI: 1750 Choke Size: 18/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1081 API Gravity Oil: 0

Tubing Size: 2 + 3/8 Tubing Setting Depth: 9472 Tbg setting date: 01/22/2018 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kellye Garcia

Title: Land & Regulatory Tech Date: _____ Email kgarcia@terraep.com
:

Attachment Check List

Att Doc Num **Name**

401543503	FORM 5A SUBMITTED
401543519	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

User Group **Comment**

Comment Date

		Stamp Upon Approval
--	--	------------------------

Total: 0 comment(s)