

FORM  
5Rev  
09/14

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401473515

Date Received:

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

OGCC Operator Number: 10456

Contact Name: Reed Haddock

Name of Operator: CAERUS PICEANCE LLC

Phone: (720) 880-6369

Address: 1001 17TH STREET #1600

Fax: (303) 565-4606

City: DENVER State: CO Zip: 80202

API Number 05-045-23386-00

County: GARFIELD

Well Name: Puckett

Well Number: 11C-26 697

Location: QtrQtr: SESW Section: 23 Township: 6S Range: 97W Meridian: 6

Footage at surface: Distance: 652 feet Direction: FSL Distance: 2491 feet Direction: FWL

As Drilled Latitude: 39.503028 As Drilled Longitude: -108.187911

## GPS Data:

Date of Measurement: 02/13/2018 PDOP Reading: 1.2 GPS Instrument Operator's Name: Bart Hunting

\*\* If directional footage at Top of Prod. Zone Dist.: 735 feet. Direction: FNL Dist.: 294 feet. Direction: FWL

Sec: 26 Twp: 6S Rng: 97W

\*\* If directional footage at Bottom Hole Dist.: 735 feet. Direction: FNL Dist.: 294 feet. Direction: FWL

Sec: 26 Twp: 6S Rng: 97W

Field Name: GRAND VALLEY

Field Number: 31290

Federal, Indian or State Lease Number:

Spud Date: (when the 1st bit hit the dirt) 12/02/2017 Date TD: 12/08/2017 Date Casing Set or D&amp;A: 12/08/2017

Rig Release Date: 12/09/2017 Per Rule 308A.b.

## Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

Total Depth MD 9380 TVD\*\* 8910 Plug Back Total Depth MD 9351 TVD\*\* 8881

Elevations GR 8432 KB 8462 Digital Copies of ALL Logs must be Attached per Rule 308A ☐

## List Electric Logs Run:

CBL, PNL

## CASING, LINER AND CEMENT

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	20	53#	0	100	218	0	100	CALC
SURF	14+3/4	9+5/8	36#	0	2,527	866	0	2,527	CALC
1ST	8+3/4	4+1/2	11.6#	0	9,358	941	3,920	9,358	CALC

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

## FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analysis must be submitted to COGCC)
	Top	Bottom	DST	Cored	
GREEN RIVER	0	3,496	NO	NO	
WASATCH	3,496	4,714	NO	NO	
WASATCH G	4,714	5,013	NO	NO	
FORT UNION	5,013	6,277	NO	NO	
OHIO CREEK	6,277	6,471	NO	NO	
WILLIAMS FORK	6,471	8,655	NO	NO	
CAMEO	8,655	9,125	NO	NO	
ROLLINS	9,125		NO	NO	

Comment:

All casing and cement information and formation tops are measured from KB. Per the approved Form 2 APD for the subject well, one gamma ray and one resistivity log was required for this multi-well pad. Please refer to the open hole logs submitted with the Puckett 24A-23-697 (API# 05-045-23388).

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Reed Haddock

Title: Sr. Regulatory Specialist

Date: \_\_\_\_\_

Email: rhaddock@caerusoilandgas.com

### Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
401478750	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
401481421	Directional Survey **	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
401481423	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401529704	PDF-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401529706	PDF-PULSED NEUTRON	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401529707	LAS-PULSED NEUTRON	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401529710	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
401545216	WELL LOCATION PLAT	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
		Stamp Upon Approval

Total: 0 comment(s)