

Ranger Energy Services, LLC  
800 Gessner, Suite 1000  
Houston, TX 77024  
(713) 935-8900  
(713) 935-8901 (FAX)



103638

Cement Ticket


Rig #

Third Party

Customer Name	Date Of Service:
Bill Barrett Corporation	1/20/2018

Location	Equipment
Crystal State 13-4	C1002

Billing



Description Of Work	Start Time 06:00 am	Stop Time 08:00 pm
Drive to location sign JSA spotting equipment have a safety meeting with rig crew sign JSA rig up equipment pressure test 1000 psi ( mix 490 sx 100.40 bbls 15. 8 # slurry CGNC verify by mud scale ) pump 3 separate plugs ( tubing work string 2 3/8 ph 6, 9" open hole 8 5/8 surface casing ) ( 1 ) at 2500' 120 sx 24.59 bbls slurry displace 6. 5 bbls fresh water ( 2 ) at 1000' 120 sx 24.59 bbls slurry displace 3 bbls fresh water ( 3 ) at 500' a shoe plug pump 234 sx 47.95 bbls to surface lay down tubing ND BOPs top off well with 16 sx 3.27 bbls slurry wash equipment rig down and move out of location		

Payroll Section						
	Employee	Emp #	Rev Hrs.	Travel Hrs.	Non Rev Hrs.	Total
Supervisor	Jaime, Gustavo	HGR010484	0.00	0.00	0.00	0.00
Operator	Cisneros, Hector	HGR010397	14.00	0.00	0.00	14.00
Derrick	Garcia, Roger	HGR010713	14.00	0.00	0.00	14.00
FloorHand	Campa, Nicolas	HGR010815	14.00	0.00	0.00	14.00

No Unreported Incidents Per  
My Signature

Ranger Tool Pusher

Customer/Agent: