



GENERAL NOTES:

1. SS PIPE > 2" SCH80S,  
SS PIPE ≤ 2" SCH160S
2. CLASS 900# FLANGES EXCEPT FOR 1500# CHOKE
3. MAG FLOW METER 5 PIPE DIA UPSTREAM, 2 PIPE DIA. DOWNSTREAM
4. BURIAL DEPTH ACROSS LOCATION > 4'
5. MATCH 10" TEE LENGTH TO EXISTING TEE LENGTH
6. TAKE BACK SS TO NEXT GOOD EXISTING FRP FLANGE

REVISIONS									
A	FIRST SKETCH	TLD 12/05/17	/	/	-				
B	POST OPERATOR REVIEW	TLD 12/12/17	/	/	-				
C	LINE SIZE CHANGE 6" TO 4"	TLD 01/15/18	/	/	-				

FOR REVIEW

Chevron U.S.A. Inc.		RANGELY WEBER SAND UNIT RIO BLANCO COUNTY, COLORADO	
EMERALD 79X SWD CONVERSION – PROCESS AND INSTRUMENTATION DIAGRAM		RANGE-XXXXXXXXX-PRO-PID-MCB-XXXX	
DR. TLD ENG. *			