

Well Summary Report

(Lifestyle) State 1-4 2/6/2018 06:00 - 2/7/2018 06:00

API 05-123-09837	State/Province Colorado	County Weld	Field Name Non-Operated	Well Status 123: Permanent PA	Total Depth (ftKB)	Primary Job Type Abandon Well
---------------------	----------------------------	----------------	----------------------------	----------------------------------	--------------------	----------------------------------

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	1.00	07:00	CTRL	Crew Travel		
07:00	0.25	07:15	SRIG	Rig Up/Down	Fire Up equip, safety meeting, MU 6 1/8" Bit	
07:15	0.75	08:00	TRIP	Tripping	TIH 10 stands, EOT @ 321'	
08:00	0.25	08:15	SRIG	Rig Up/Down	RU power swivel	
08:15	8.50	16:45	RUTB	Run Tubing	Continue Washing to TD, circulating hole, TD @ 2500', circulate hole clean.	
16:45	1.25	18:00	TRIP	Tripping	RD Power Swivel, TOO, stand back 74 JNTs 2 3/8" PH6, LD 1 single & 6- 3.5" DCs	
18:00	0.50	18:30	SRIG	Rig Up/Down	Winterize Equip, secure WH, prep for cementers in AM, SDFN	
18:30	1.00	19:30	CTRL	Crew Travel		
19:30	10.50	06:00	LOCL	Lock Wellhead & Secure		

(Lifestyle) State 1-4 2/7/2018 06:00 - 2/8/2018 06:00

API 05-123-09837	State/Province Colorado	County Weld	Field Name Non-Operated	Well Status 123: Permanent PA	Total Depth (ftKB)	Primary Job Type Abandon Well
---------------------	----------------------------	----------------	----------------------------	----------------------------------	--------------------	----------------------------------

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	1.00	07:00	CTRL	Crew Travel		
07:00	4.00	11:00	SRIG	Rig Up/Down	Fire Equip, safety meeting, wait for cementers to be near location	
11:00	1.00	12:00	TRIP	Tripping	TIH w/ 81 JNTs 2 3/8" PH6 TBG EOT @ 2500'	
12:00	3.50	15:30	CLN	Clean Out Hole	Circulate hole, waiting for cement crew to return to location	
15:30	0.50	16:00	SRIG	Rig Up/Down	RU Ranger Cement Equip, hold safety meeting	
16:00	0.50	16:30	CEMT	Balanced Plug	Pump 1st plug: pump 5bbl fresh establish circulation /120sks, 1.15yield, 15.8ppg, class G cement, 24.5bbls slurry/6.5bbls displacement	
16:30	2.75	19:15	TRIP	Tripping	TOOH, stand by for cement to cure, TIH tag cement @ 2356', POOH to 1500'	
19:15	0.50	19:45	CEMT	Balanced Plug	Pump 2nd plug: pump 5bbl fresh establish circulation /120sks, 1.15yield, 15.8ppg, class G cement, 24.5bbls slurry/3.5bbls displacement	
19:45	0.50	20:15	TRIP	Tripping	TOOH, Secure WH, SDFN	
					RD Ranger Cementers	
20:15	1.00	21:15	CTRL	Crew Travel		
21:15	8.75	06:00	LOCL	Lock Wellhead & Secure		

(Lifestyle) State 1-4 2/8/2018 06:00 - 2/9/2018 06:00

API 05-123-09837	State/Province Colorado	County Weld	Field Name Non-Operated	Well Status 123: Permanent PA	Total Depth (ftKB)	Primary Job Type Abandon Well
---------------------	----------------------------	----------------	----------------------------	----------------------------------	--------------------	----------------------------------

Time Log						
Start Time	Dur (hr)	End Time	Code	Category	Com	
06:00	1.00	07:00	LOCL	Lock Wellhead & Secure		
07:00	1.00	08:00	CTRL	Crew Travel		
08:00	0.50	08:30	SRIG	Rig Up/Down	Fire up equip, safety meeting	
08:30	0.75	09:15	TRIP	Tripping	TIH, tag 2nd cement plug @ 1148', TOO	
09:15	2.75	12:00	GOP	General Operations	Stand by for cementers	
12:00	0.25	12:15	TRIP	Tripping	TIH to 440'	
12:15	0.75	13:00	SRIG	Rig Up/Down	RU Ranger Cement Equip. hold safety meeting	
13:00	1.00	14:00	CEMT	Surface Plug	Pump surface plug, 5bbls fresh establish circulation/ 440sks, 1.15yield, 15.8ppg, class G cement, 90bbls, saw returns to surface after 87bbls,	
14:00	0.75	14:45	PULT	Pull Tubing	POOH, RD rig floor, ND BOPs & flange, top wellbore off with cement, wash up cement equip.	
14:45	3.25	18:00	SRIG	Rig Up/Down	RDMO ranger Cement Equip. RDMO Ensign rig #312 & Equipment	
18:00	12.00	06:00	LOCL	Lock Wellhead & Secure		