

UPRR C#1

659 FSL1980 FEL C SWSE 21 4N 63W 6th PM

Lat 40.292178 Long -104.440981

Weld County, Colorado

API #05-123-05139

Spud date 9/30/1954

4589 KB
0 GL

101 sx cement
442' to surface

7", 26# @ 388'

9.625", 25.4#/ft Wt, Grade, 397, 12.25" hole
Cemented to surface w/320 sx.

382 sx cement plug
784' - 442'

As found in well:
UPRR C#1,

450 sx cement plug
3500' - 2614'

Niobrara 6525 '

J Sand 7241 '

Lyons 8444 '

Cement plug
7120' - 7380'

TD 8603 ft

Updated 3/15/2018 rcs