

CURRENT WBD			Enerplus Resources			
	***** ** MUD ** *****	10 sks	WELL:	Thayer 2	FIELD:	Black Hollow NW
		25 sks	LOCATION:	NENW Sec 26-T8N-R67E, Weld Co, CO		
305'	25 sks	8-5/8"	ACCTG CODE:	STATUS: PA		
515'		Fox Hills base	ELEVATION:	GL - 5,265'	API NO	05-123-11778
			SPUD DATE:	4/26/1984	COMP DATE:	6/12/1984
			MEASURED TD	7,496'	TVD:	7,496'
4,858'		Shannon Top	SURF CSG:	8-5/8" 24# set at 305'. Cmtd with 200 sks.		
			PROD CSG:	4-1/2" 10.5/11.6# set at 7,489' Cmtd with 150 sks		
4,962'		Shannon Base	FORMATION:	DEPTH:		
			Fox Hills	515'	base	***Deepest water well 420'
			Parkman	3,502'	top	
			Sussex	4,453'	top	
			Shannon	4,858'	top	
			Niobrara	7,081'	top	
			Codell	7,420'	top	
			<u>Original Completion:</u>			
6,700'		CBL TOC	7,210'-7,232'			
			2 spf, 3/18" SSR 12 gram			
			17,220 gal 30QSF40 w/ 4,000# 100 mesh, 27,000# 20/40 sand			
			7,210'-7,232'			
			2 spf, 3/18" SSR 12 gram			
			84,756 gal YF40 w/ 15,000# 100 mesh, 120,000# 20/40 sand			
7,081'	5 sks	Niobrara Top	<u>Original PA:</u>			
	** 7,100' **		Ran sand plug at 7,300'			
	*****		5 sks of cmt at 7,300'			
	*****		Ran sand plug from 7,300'-7,100'			
7,210'-7,212'	= ***** =	Perfs	5 sks of cmt at 7,100'			
7,216'-7,218'	= ** SAND ** =	Perfs	25 sks of cmt at 315'			
7,222'-7,232'	= ***** =	Perfs	Mudded to 28'			
	*****		10 sks of cmt in top of surface pipe			
	*****		Welded on cap			
	5 sks					
	** 7,300' **					

7,420'	** SAND **	Codell Top				
7,425'-7,435'	= ***** =	Perfs				

7,477'		MPBD				
TD - 7,496'			Prepared by:	Cody Clickner	3/14/2018	