

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

401580686

Receive Date:

03/20/2018

Report taken by:

BOB CHESSON

Site Investigation and Remediation Workplan (Supplemental Form)

This form shall be submitted to the Director for approval prior to the initiation of site investigation and remediation activities. However, this shall not preclude the Operator from taking immediate action to protect public health or safety, the environment, wildlife, or livestock.

This Form 27 describes site conditions as currently understood by the Operator; approval of this Form 27 by COGCC is based on the site conditions accurately described herein; any changes in site conditions identified during or subsequent to the performance of the approved workplan may necessitate additional investigation or remediation which shall be described on a supplemental Form 27. This Form 27 is intended to provide basic information regarding the proposed site investigation and remediation actions, but the workplan may be more fully described in attached documentation.

Refer to Rules 340, 905, 906, 907, 908, 909, and 910

OPERATOR INFORMATION

Name of Operator: NOBLE ENERGY INC	Operator No: 100322	Phone Numbers Phone: (970) 3045329 Mobile: ()
Address: 1001 NOBLE ENERGY WAY		
City: HOUSTON	State: TX Zip: 77070	
Contact Person: Jacob Evans	Email: jacob.evans@nblenergy.com	

PROJECT, PURPOSE & SITE INFORMATION

PROJECT INFORMATION

Remediation Project #: 9150 Initial Form 27 Document #: 2143666

PURPOSE INFORMATION

- | | |
|--|--|
| <input checked="" type="checkbox"/> 901.e. Sensitive Area Determination | <input checked="" type="checkbox"/> 909.c.(5), Rule 910.b.(4): Remediation of impacted ground water |
| <input type="checkbox"/> 909.c.(1), Rule 905: Pit or PW vessel closure | <input type="checkbox"/> Rule 909.e.(2)A.: Notice completion of remediation in accordance with Rule 909.b. |
| <input checked="" type="checkbox"/> 909.c.(2), Rule 906: Spill/Release Remediation | <input type="checkbox"/> Rule 909.e.(2)B.: Closure of remediation project |
| <input type="checkbox"/> 909.c.(3), Rule 907.e.: Land treatment of oily waste | <input type="checkbox"/> Rule 906.c.: Director request |
| <input type="checkbox"/> 909.c.(4), Rule 908.g.: Centralized E&P Waste Management Facility closure | <input type="checkbox"/> Other |

SITE INFORMATION

N Multiple Facilities (in accordance with Rule 909.c.)

Facility Type: SPILL OR RELEASE	Facility ID: 441780	API #:	County Name: WELD
Facility Name: SPILL/RELEASE POINT		Latitude: 40.304656	Longitude: -104.654142
		** correct Lat/Long if needed: Latitude:	Longitude:
QtrQtr: NENW	Sec: 22	Twp: 4N	Range: 65W Meridian: 6 Sensitive Area? Yes

SITE CONDITIONS

General soil type - USCS Classifications SC Most Sensitive Adjacent Land Use Agricultural Land

Is domestic water well within 1/4 mile? No Is surface water within 1/4 mile? Yes

Is groundwater less than 20 feet below ground surface? Yes

Other Potential Receptors within 1/4 mile

Surface water 1069'W

SITE INVESTIGATION PLAN

TYPE OF WASTE:

☒ E&P Waste

☐ Other E&P Waste

☐ Non-E&P Waste

☒ Produced Water

☐ Workover Fluids

☐ Oil

☐ Tank Bottoms

☐ Condensate

☐ Pigging Waste

☐ Drilling Fluids

☐ Rig Wash

☐ Drill Cuttings

☐ Spent Filters

☐ Pit Bottoms

☐ Other (as described by EPA)

DESCRIPTION OF IMPACT

Impacted?	Impacted Media	Extent of Impact	How Determined
Yes	GROUNDWATER	180 X 120	Lab Analytical
Yes	SOILS	45' X 54' X 7' bgs	Lab Analytical

INITIAL ACTION SUMMARY

Description of initial action or emergency response measures take to abate, investigate, and/or remediate impacts associated with E&P Waste.

The facility was shut in and a site assessment was scheduled. Refer to Spill/Release Report

Document #400840208.

PROPOSED SAMPLING PLAN

Proposed Soil Sampling

☒ Will soil samples be collected as part of this investigation? (Number, type (grab/composite), analyses, and locations of samples):

Twenty seven (27) soil samples were collected and analyzed for TPH-DRO, TPH-GRO, BTEX, and Naphthalene to confirm source impacts were remediated.

Proposed Groundwater Sampling

☒ Will groundwater samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Nineteen (19) groundwater samples were collected during site investigation activities to determine the extent of dissolved phase BTEX.

Proposed Surface Water Sampling

☐ Will surface water samples be collected as part of this investigation? (Number, analyses, and locations of samples):

Additional Investigative Actions

☐ Additional alternative investigative actions described in attached Site Investigation Plan (summary):

SITE INVESTIGATION REPORT

SAMPLE SUMMARY

Soil

Number of soil samples collected 27

Number of soil samples exceeding 910-1 1

Was the areal and vertical extent of soil contamination delineated? Yes

Approximate areal extent (square feet) 2430

NA / ND

-- Highest concentration of TPH (mg/kg) 240

-- Highest concentration of SAR 0.771

BTEX > 910-1 Yes

Vertical Extent > 910-1 (in feet) 7

Groundwater

Number of groundwater samples collected 19

Was extent of groundwater contaminated delineated? Yes

Depth to groundwater (below ground surface, in feet) 7'

Number of groundwater monitoring wells installed 19

Number of groundwater samples exceeding 910-1 15

-- Highest concentration of Benzene (µg/l) 31000

-- Highest concentration of Toluene (µg/l) 18000

-- Highest concentration of Ethylbenzene (µg/l) 3800

-- Highest concentration of Xylene (µg/l) 54000

NA Highest concentration of Methane (mg/l)

Surface Water

0 Number of surface water samples collected

0 Number of surface water samples exceeding 910-1

If surface water is impacted, other agency notification may be required.

OTHER INVESTIGATION INFORMATION

☐ Were impacts to adjacent property or offsite impacts identified?

☐ Were background samples collected as part of this site investigation?

☐ Was investigation derived waste (IDW) generated as part of this investigation?

Volume of solid waste (cubic yards)

Volume of liquid waste (barrels)

☐ Is further site investigation required?

REMEDIAL ACTION PLAN

Does this Supplemental Form 27A include changes to a previously approved Remedial Action Plan? No _____

SOURCE REMOVAL SUMMARY

Describe how source is to be removed.

Impacted soil will be excavated and treated onsite by chemical oxidation using hydrogen peroxide. The stockpiled soil will be processed through a soil shredder, and sprayed with hydrogen peroxide as it passes through the shredder. After confirmation analytical testing is complete, treated soil will be used as backfill material.

REMEDIATION SUMMARY

Describe how remediation of existing impacts to soil and groundwater is to be accomplished (i.e. summarize remedial action plan). Provide a brief narrative description including: technical justification, schedule for implementation, estimated time to attain NFA status, plus plans and specifications for the selected remedial action technology.

An air sparge and soil vapor extraction remediation system was installed to treat residual soil and dissolved phase groundwater. Twenty (20) monitoring wells were included in the 1st quarter 2017 sampling plan and will be sampled for BTEX on a quarterly basis to monitor the dissolved BTEX plume and ensure it is stable and decreasing.

Soil Remediation Summary

☒ In Situ

No _____ Bioremediation (or enhanced bioremediation)
No _____ Chemical oxidation
Yes _____ Air sparge / Soil vapor extraction
Yes _____ Natural Attenuation
No _____ Other _____

☒ Ex Situ

No _____ Excavate and offsite disposal
If Yes: Estimated Volume (Cubic Yards) _____
Name of Licensed Disposal Facility or COGCC Facility ID # _____
Yes _____ Excavate and onsite remediation
No _____ Land Treatment
No _____ Bioremediation (or enhanced bioremediation)
Yes _____ Chemical oxidation
No _____ Other _____

Groundwater Remediation Summary

No _____ Bioremediation (or enhanced bioremediation)
No _____ Chemical oxidation
Yes _____ Air sparge / Soil vapor extraction
Yes _____ Natural Attenuation
No _____ Other _____

GROUNDWATER MONITORING

If groundwater has been impacted, describe proposed monitoring plan, including # of wells or sample points, monitoring schedule, analytical methods, points of compliance. Attach a groundwater monitoring location diagram.

Twenty (20) monitoring wells including BH01R, BH02R, BH04R, BH08R, BH12R, BH17, BH20, BH21, BH22, BH23, BH24, BH25, BH26, BH27, BH28, BH29, BH30, BH31, and BH33 will be sampled and analyzed for BTEX on a quarterly basis.

REMEDATION PROGRESS UPDATE

PERIODIC REPORTING

Frequency: ☐ Quarterly ☐ Semi-Annually ☒ Annually ☐ Other _____

Report Type: ☒ Groundwater Monitoring ☐ Land Treatment Progress Report ☐ O&M Report
☐ Other _____

WASTE DISPOSAL INFORMATION

Was E&P waste generated as part of this remediation? Yes _____

Describe beneficial use, if any, of E&P Waste derived from this remediation project:

During source remediation soil shredding with hydrogen peroxide was utilized to remediate hydrocarbon impacted soil above COGCC Table 910-1 standards.

Volume of E&P Waste (solid) in cubic yards 772

E&P waste (solid) description Impacted soil above COGCC Table 910-1 standards

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: Beneficial reuse _____

Volume of E&P Waste (liquid) in barrels 0

E&P waste (liquid) description _____

COGCC Disposal Facility ID #, if applicable: _____

Non-COGCC Disposal Facility: _____

REMEDATION COMPLETION REPORT

REMEDATION COMPLETION SUMMARY

Is this a Final Closure Request for this Remediation Project? No _____

Do all soils meet Table 910-1 standards? No _____

Does the previous reply indicate consideration of background concentrations? _____

Are the only residual soil impacts pH, SAR, or EC at depths greater than 3 feet below ground surface? No _____

Does Groundwater meet Table 910-1 standards? No _____

Is additional groundwater monitoring to be conducted? Yes _____

RECLAMATION PLAN

RECLAMATION PLANNING

Describe reclamation plan. Discuss existing and new grade recontouring; method and testing of compaction alleviation; and reseeding program, including location of new seed, seed mix and noxious weed prevention. Attach diagram or drawing.

Reclamation will be in compliance with the COGCC 1000 series rule. In addition, subsequent to receipt of a No Further Action (NFA) designation, monitoring wells and remediation wells will be properly plugged and abandoned per Colorado Division of Water Resources standards.

Is the described reclamation complete? _____

Does the reclamation described herein constitute interim or final reclamation of the Oil and Gas Location?

☐ Interim? ☐ Final?

Did the Surface Owner approve the seed mix? _____

If NO, does the seed mix comply with local soil conservation district recommendations? _____

IMPLEMENTATION SCHEDULE

PRIOR DATES

Date of Surface Owner notification/consultation, if required. _____

Actual Spill or Release date, if known. _____

SITE INVESTIGATION DATES

Date of Initial Actions described in Site Investigation Plan (start date). _____

Date of commencement of Site Investigation. 06/05/2015

Date of completion of Site Investigation. _____

REMEDIAL ACTION DATES

Date of commencement of Remediation. 06/19/2015

Date of completion of Remediation. _____

SITE RECLAMATION DATES

Date of commencement of Reclamation. _____

Date of completion of Reclamation. _____

OPERATOR COMMENT

Chesnut G22-3,4

I hereby certify all statements made in this form are to the best of my knowledge true, correct, and complete.

Signed: Jacob Evans

Title: Environmental Coordinator

Submit Date: 03/20/2018

Email: jacob.evans@nblenergy.com

Based on the information provided herein, this Application for Site Investigation and Remediation Workplan complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: BOB CHESSON

Date: 03/20/2018

Remediation Project Number: 9150

COA Type

Description

--	--

Attachment Check List

Upon approval, the approved Form 27 and all listed attachments will be indexed to the Remediation Project file. Only the approved Form 27 will also be indexed to the related Facilities.

Att Doc Num

Name

401580686	FORM 27-SUPPLEMENTAL-SUBMITTED
401580695	MONITORING REPORT

Total Attach: 2 Files

General Comments

User Group

Comment

Comment Date

		Stamp Upon Approval
--	--	---------------------

Total: 0 comment(s)