

**FORM
INSP**

Rev
X/15

**State of Colorado
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203
Phone: (303) 894-2100 Fax: (303) 894-2109



Inspection Date:

03/15/2018

Submitted Date:

03/16/2018

Document Number:

679700824

FIELD INSPECTION FORM

Loc ID 331970 Inspector Name: ALLISON, RICK On-Site Inspection 2A Doc Num: _____

Status Summary:

- THIS IS A FOLLOW UP INSPECTION
- FOLLOW UP INSPECTION REQUIRED
- NO FOLLOW UP INSPECTION REQUIRED

Operator Information:

OGCC Operator Number: 36200
Name of Operator: GRYNBERG* JACK DBA GRYNBERG PETROLEUM CO
Address: 3600 S. YOSEMITE ST - STE 900
City: DENVER State: CO Zip: 80237-

Findings:

- 4 Number of Comments
- 1 Number of Corrective Actions
- Corrective Action Response Requested

Contact Information:

Contact Name	Phone	Email	Comment
Grynberg Petroleum		grynpetro@grynberg.com	
Randy Edelen		r.edelen@grynberg.com	
Pesicka, Conor		conor.pesicka@state.co.us	

Inspected Facilities:

Facility ID	Type	Status	Status Date	Well Class	API Num	Facility Name	Insp Status
454026	SPILL OR RELEASE	AC	02/20/2018		-	Croissant 4	EI

General Comment:

[COGCC Environmental Inspection of Croissant #4 release](#)

Inspected Facilities

Facility ID: 454026 Type: SPILL OR API Number: - Status: AC Insp. Status: EI

Environmental

Waste Management:

Type	Management	Condition	GPS (Lat) (Long)
Oily Soil	Other	Adequate	
Comment	Operator is conducting an excavation and hauling material for commercial disposal with limited stockpiling. Operator indicates all material is being hauled to Waste Management in Ault for disposal.		
Corrective Action			Date:

Spill/Remediation:

Comment:	Operator is conducting excavation in area of surface impact caused by produced water spill from flowline likely serving the Croissant 1 disposal well. Operator indicated portion of disposal flowline has been removed from excavation. All flowlines from Croissant 4 will be cut, flushed and capped. Operator indicates CIBP is present in Croissant 4. Unknown when production will resume.		
Corrective Action:	Continue to investigate spill and report results of investigation and remediation using Form 19 Supplemental Report. Submit site diagram showing investigation extents and soil sample locations. Submit results of soil confirmation sample locations. Comply with COAs on Form 19 Document #401548555 (reiterated and end of this inspection). Corrective Action Date reflects date Form 19 is due.		Date: 06/13/2018

Emission Control Burner (ECB): _____

Comment: _____

Pilot: _____ Wildlife Protection Devices (fired vessels): _____

COGCC Comments

Comment	User	Date
<p>Conditions of Approval from Form 19 Document #401548555:</p> <p>Discrete soil samples must be collected to determine the vertical and horizontal extent of impacts to soil in accordance with Rule 910. Soil samples must be collected from the floor and sidewalls of any excavation and from surface areas impacted by the release. Analyze all soil samples for BTEX, TPH-GRO, TPH-DRO, pH, EC, and SAR.</p> <p>Investigate source of dead vegetation. Investigation must include pressure testing of flowlines in accordance with Rule 1102.e. at a minimum. Provide results of pressure testing on a Supplemental Form 19.</p>	allisonr	03/16/2018

Attached Documents

You can go to COGCC Images (<https://cogcc.state.co.us/weblink/>) and search by document number:

Document Num	Description	URL
401577341	INSPECTION SUBMITTED	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4405545
679700828	Croissant 4 Excavation Photos 3-15-2018	http://ogccweblink.state.co.us/DownloadDocumentPDF.aspx?DocumentId=4405541