

FORM  
5A

Rev  
06/12

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401589285

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850  
2. Name of Operator: TEP ROCKY MOUNTAIN LLC  
3. Address: PO BOX 370  
City: PARACHUTE State: CO Zip: 81635  
4. Contact Name: Kellye Garcia  
Phone: (832) 726-1159  
Fax:  
Email: kgarcia@terraep.com

5. API Number 05-045-23435-00  
6. County: GARFIELD  
7. Well Name: WARE  
Well Number: SR 514-12  
8. Location: QtrQtr: NESW Section: 12 Township: 7S Range: 94W Meridian: 6  
9. Field Name: RULISON Field Code: 75400

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 03/02/2018 End Date: 03/07/2018 Date of First Production this formation: 03/21/2018

Perforations Top: 8054 Bottom: 9938 No. Holes: 480 Hole size: 35/100

Provide a brief summary of the formation treatment: Open Hole: ☐

50664 bbls of slickwater; 955350 100/Mesh; 1294 gals of biocide

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 50695 Max pressure during treatment (psi): 8584

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.74

Total acid used in treatment (bbl): Number of staged intervals: 10

Recycled water used in treatment (bbl): 50664 Flowback volume recovered (bbl): 16513

Fresh water used in treatment (bbl): Disposition method for flowback: RECYCLE

Total proppant used (lbs): 955350 Rule 805 green completion techniques were utilized: ☐

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 03/23/2018 Hours: 24 Bbl oil: 0 Mcf Gas: 1039 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 1039 Bbl H2O: 0 GOR: 0

Test Method: FLOWING Casing PSI: 2000 Tubing PSI: 1575 Choke Size: 18/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1107 API Gravity Oil: 0

Tubing Size: 2 + 3/8 Tubing Setting Depth: 9736 Tbg setting date: 03/18/2018 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kellye Garcia

Title: Land & Regulatory Tech Date: \_\_\_\_\_ Email kgarcia@terraep.com  
:

### Attachment Check List

**Att Doc Num**      **Name**

401589287	WELLBORE DIAGRAM
-----------	------------------

Total Attach: 1 Files

### General Comments

**User Group**      **Comment**

**Comment Date**

		Stamp Upon Approval
--	--	------------------------

Total: 0 comment(s)