

VERBAL REQUEST

NOTICE OF INTENTION TO DRILL _____

Bonding Status _____

NOTICE OF INTENTION TO ABANDON X

OTHER Dowdell (Cont.)

COMPANY Viking Pet. Inc. ADDRESS _____

BY Stan Mollerstuen Geol. PHONE NO. 623-7832
Title Extension

WELL NO. 40-1A LEASE No. Poudre

COUNTY Carimar FIELD Wellington

Location NW NE Sec. 19 Twp. 9 N Range 68 W Meridian 6

220 feet from N Section line, and 2580 feet from E Section Line
N or S E or W

ESTIMATED DATE OF WORK 6-15-77 ESTIMATED TIME —

DETAILS OF PLAN OF WORK: T.D. 4810 FORMATION Muddy

SURFACE CASING 8 5/8" @ 298'

5 1/2" @ 4809' Perfs. 4698' - 4718'


Sand plus 5 sat over perfs.

Shoot + pull pipe - 15 sat on stub of pipe

15 sat @ 298'

10 sat @ surface w/ plate

APPROVED BY J. A. Mc Kee DATE 6-7-77



00222274

X₆