

Cementer's Well Service, Inc.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

Synergy Resources Corporation - Surface Cement Data Sheet



CEMENTER'S
—WELL SERVICE, INC.—

5/31/2017		Well Owner: Synergy		Well No. 1C-23-L	
County WELD		State CO		Lease Leffler	
Client Synergy Resources Corporation					
Address 1625 Broadway					
City Denver		State CO		80202	
Type of Job	Surface	Depth	1785 ft.	Time On	600
Surface	9 5/8 csg 36# 13 1/2 Hole	Bottom of Surface	1763 ft.	Plug Down	915
		Plug Landed @	1718 ft.		
		Pipe Landed @	1763 ft.		
Other:					
Description		Quantity	Meas.		
Data Acquisition	* see attached graph and data	1			
Cement Neat		720	SKS		
Calcium Chloride		1.5	%		
Gel	3%		%		
Mileage Heavy		40	Miles		
Mileage Pick-Up			Miles		
Mud Flush		1			
Additional Cement			SKS		
Mixing Rate	4bpm				
Disp. Rate	5bpm				
Slurry Vol.	1.61cuft*3 sk				
Slurry Wt.	13.9ppg				
Water/Cement	8.2 gals sk				
Water Temp.	60 degrees				
Total Slurry Vol.	206.4	BBLS Cement			
Landed Plug @	1175	PSI / Final Lift @	625	PSI	
Pre-Flush W/	10 Fresh 20 Flush	BBLS H ² O			
Displace W/	132.8	BBLS H ² O			
Circulate	30	BBLS Cement			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming
1202		Pump Truck		20	
1216/1234		Bulk Truck	20/20		
					Total Mileage

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By _____

Received By _____

Customer or His Agent