

# Cementer's Well Service, Inc.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

## Synergy Resources Corporation - Surface Cement Data Sheet



**CEMENTER'S**  
—WELL SERVICE, INC.—

5/30/2017		Well Owner: Synergy		Well No. 41N-23C-L	
County WELD		State CO		Lease Leffler	
Client Synergy Resources Corporation					
Address 1625 Broadway					
City Denver		State CO		80202	
Type of Job	Surface	Depth	1782 ft.	Time On	1100
Surface	9 5/8 csg 36# 13 1/2 Hole	Bottom of Surface	1776 ft.	Plug Down	1309
		Plug Landed @	1732 ft.		
		Pipe Landed @	1776 ft.		
Other:					
Description		Quantity	Meas.		
Data Acquisition	* see attached graph and data	1			
Cement Neat		740	SKS		
Calcium Chloride		1.5	%		
Gel		3	%		
Mileage Heavy	(2) Bulk & Trailer		Miles		
Mileage Pick-Up		40	Miles		
Mud Flush		1			
Additional Cement			SKS		
Mixing Rate	4bpm				
Disp. Rate	5bpm				
Slurry Vol.	1.61cuft*3 sk				
Slurry Wt.	13.8 ppg				
Water/Cement	8.2 gals sk				
Water Temp.	46				
Total Slurry Vol.	212.0	BBLS Cement			
Landed Plug @	1240	PSI / Final Lift @	675	PSI	
Pre-Flush W/	10 Fresh 20 Flush	BBLS H <sup>2</sup> O			
Displace W/	133.8	BBLS H <sup>2</sup> O			
Circulate	20	BBLS Cement			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming
1201		Pump Truck		15	
1234/1217		Bulk Truck	15/15		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By \_\_\_\_\_

Received By \_\_\_\_\_

Customer or His Agent