

# Cementer's Well Service, Inc.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

## Synergy Resources Corporation - Surface Cement Data Sheet



**CEMENTER'S**  
—WELL SERVICE, INC.—

5/29/2017		Well Owner: Synergy		Well No. 41C-23-L	
County WELD		State CO		Lease Leffler	
Client Synergy Resources Corporation					
Address 1625 Broadway					
City Denver		State CO		80202	
<b>Type of Job</b>	Surface	Depth	1775 ft.	Time On	1600
	Surface 9 5/8 csg 36# 13 1/2 Hole	Bottom of Surface	1763 ft.	Plug Down	1945
		Plug Landed @	1719 ft.	Other:	
		Pipe Landed @	1763 ft.		
<b>Description</b>		<b>Quantity</b>	<b>Meas.</b>		
Data Acquisition	* see attached graph and data	1			
Cement Neat		730	SKS		
Calcium Chloride		1.5	%		
Gel	3%		%		
Mileage Heavy		40	Miles		
Mileage Pick-Up			Miles		
Mud Flush		1			
Additional Cement			SKS		
Mixing Rate	4bpm				
Disp. Rate	5bpm				
Slurry Vol.	1.61cuft*3 sk				
Slurry Wt.	13.9ppg				
Water/Cement	8.2 gals sk				
Water Temp.	61 degrees				
Total Slurry Vol.	209.3	BBLs Cement			
Landed Plug @	1075	PSI / Final Lift @	590	PSI	
Pre-Flush W/	10 Fresh 20 Flush	BBLs H <sup>2</sup> O			
Displace W/	132.8	BBLs H <sup>2</sup> O			
Circulate	32	BBLs Cement			
<b>Truck No.</b>	<b>Code</b>	<b>State Mileage</b>	<b>Nebraska</b>	<b>Colorado</b>	<b>Wyoming</b>
1202		Pump Truck		20	
1214/1234		Bulk Truck		20/20	
					<b>Total Mileage</b>

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By \_\_\_\_\_

Received By \_\_\_\_\_

Customer or His Agent