

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

401589285

Date Received:

03/28/2018

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850
2. Name of Operator: TEP ROCKY MOUNTAIN LLC
3. Address: PO BOX 370
City: PARACHUTE State: CO Zip: 81635
4. Contact Name: Kellye Garcia
Phone: (832) 726-1159
Fax:
Email: kgarcia@terraep.com

5. API Number 05-045-23435-00
6. County: GARFIELD
7. Well Name: WARE
Well Number: SR 514-12
8. Location: QtrQtr: NESW Section: 12 Township: 7S Range: 94W Meridian: 6
9. Field Name: RULISON Field Code: 75400

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 03/02/2018 End Date: 03/07/2018 Date of First Production this formation: 03/21/2018

Perforations Top: 8054 Bottom: 9938 No. Holes: 480 Hole size: 35/100

Provide a brief summary of the formation treatment: Open Hole: ☐

50664 bbls of slickwater; 955350 100/Mesh; 1294 gals of biocide

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 50695

Max pressure during treatment (psi): 8584

Total gas used in treatment (mcf):

Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment:

Min frac gradient (psi/ft): 0.74

Total acid used in treatment (bbl): 31

Number of staged intervals: 10

Recycled water used in treatment (bbl): 50664

Flowback volume recovered (bbl): 16513

Fresh water used in treatment (bbl):

Disposition method for flowback: RECYCLE

Total proppant used (lbs): 955350

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 03/23/2018 Hours: 24 Bbl oil: 0 Mcf Gas: 1039 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 1039 Bbl H2O: 0 GOR: 0

Test Method: FLOWING Casing PSI: 2000 Tubing PSI: 1575 Choke Size: 18/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1107 API Gravity Oil: 0

Tubing Size: 2 + 3/8 Tubing Setting Depth: 9736 Tbg setting date: 03/18/2018 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kellye Garcia

Title: Land & Regulatory Tech Date: 3/28/2018 Email kgarcia@terraep.com
:

Attachment Check List

Att Doc Num **Name**

401589285	FORM 5A SUBMITTED
401589287	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

User Group **Comment** **Comment Date**

Permit	-805 green completion box not checked emailed operator to see why.	04/04/2018
--------	--	------------

Total: 1 comment(s)