



PRIMARY DB KEY:
LEASE #:

NAME/DESCRIP :

JOHN CRAIG 1-2
GAS AT SEPARATOR

PROJECT NO. : 201712120
COMPANY NAME : Nighthawk Production Company
OFFICE / BRANCH: HIGHLANDS RANCH, CO
CUSTOMER REF:
PRODUCER :

ANALYSIS NO. : 19
ANALYSIS DATE: DECEMBER 27, 2017 07:29
SAMPLE DATE : DECEMBER 20, 2017 16:50
TO:
EFFECTIVE DATE:

FIELD DATA

SAMPLE CYCLE:
SAMPLE PRES. : 20 psig
FLOW PRES. : psig
LAB PRES: psig
SAMPLE TEMP. : 72.7 °f
AMBIENT TEMP.: °f
H2O BY STAIN TUBE - #/mmcf
FIELD COMMENTS:
LAB COMMENTS:

SAMPLE TYPE: SPOT
PROBE : NO
CYLINDER NO. : 0105
SAMPLED BY : JOHN MOSER
SAMPLING COMPANY: EMPACT
H2S BY STAIN TUBE: 3.0 ppm
CO2 BY STAIN TUBE: Mol %

COMPONENTS	NORM. MOLE%	GPM @ 14.73	GPM @ 14.65
HELIUM	0.39	-	-
HYDROGEN	0.00	-	-
OXYGEN/ARGON	0.09	-	-
NITROGEN	20.31	-	-
CO2	1.32	-	-
METHANE	34.69	-	-
ETHANE	15.55	4.1813	4.1586
PROPANE	17.81	4.9332	4.9065
ISOBUTANE	2.15	0.7076	0.7038
N-BUTANE	5.04	1.5977	1.5890
ISOPENTANE	0.89	0.3276	0.3258
N-PENTANE	0.87	0.3175	0.3158
HEXANES+	0.89	0.3881	0.3860
TOTAL	100.00	12.4530	12.3855

BTU @ 60 DEG F

	14.73	14.65
GROSS DRY REAL =	1435.7 /scf	1427.9 /scf
GROSS SATURATED REAL =	1410.7 /scf	1402.9 /scf
RELATIVE DENSITY (AIR=1 @14.696 PSIA 60F)	1.0595	
GRAVITY (LB/SCF)	0.08087	
COMPRESSIBILITY FACTOR :	0.99434	

NOTE: REFERENCE GPA 2261(ASM D1945 & ASME-PTC), 2145, & 2172 CURRENT PUBLICATIONS

Reference: Per GPA 2172-14 sec 9

The C6+ is derived from the following ratios of C6, C7 & C8+ respectively: 60% 30% 10%

The data presented herein has been acquired by means of current analytical techniques and represents the judicious conclusion EMPACT Analytical Systems, Inc. Results of the analysis can be affected by the sampling conditions, therefore, are only warranted through proper lab protocol. EMPACT assumes no responsibility for interpretation or any consequences from application of the reported information and is the sole liability of the user. The reproduction in any media of this reported information may not be made, in portion or as a whole, without the written permission of EMPACT Analytical Systems, Inc.