

1 copy returned
11-20-51
292-6



(Indicate nature of data by checking below)

- Notice of intention to drill. ~~XXXXXXXX~~ X
- Notice of intention to change plans
- Notice of date for test of water shut-off
- Report on result of test of water shut-off
- Notice of intention to re-drill or repair well
- Notice of intention to clean out well
- Statement of shooting
- Statement of perforating
- Notice to pull or otherwise alter casing
- Notice of intention to abandon well
- Report of work done on well since previous report

November 16 1951

Following is a (notice of intention to do work) (On land)
(~~report of work done~~) (patented) described as follows:

| | | |
|------------|----------|---|
| Colorado | Logan | Merino |
| State | County | Field |
| J-15 | Schrader | 20 (SE 1/4 NE 1/4 SE 1/4) 6N 54W 6th |
| (Well No.) | (Lease) | (Sec. and 1/4 Sec.) (Twp.) (Range) (Meridian) |

The well is located _____ ft. (N) of _____ and _____ ft. (E) of _____
(S) (W)

To be furnished later.

The elevation above sea level is/ _____ ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

We propose to drill a well using rotary tools on the above described location, the well to be known as Schrader J-15.

It is expected that approximately 150 feet of 10-3/4" OD, 32.75#/ft., H-40, 8 RT casing will be landed and cemented to the surface. This well will be drilled to the "J" sand of the Dakota formation, which is expected at approximately 5060 ft.

If commercial production is encountered, a production string consisting of 5-1/2" OD 14# J-55, 8 RT. casing will be set thru the producing formation and cemented with 150 sacks of cement. The productive zone will then be perforated.

All measurements will be taken from the Kelly Bushing.

Approved: NOV 20 1951

 State Oil Inspector
 DIRECTOR

Company Trigood Oil Company
 Address Box 1689 Casper, Wyoming
 By J. L. Fusselman
 Title Assistant Manager

Submit reports of proposed work, for approval, on this form in Duplicate.

/ib SOI (2); OI (2); Ld; Fld; JLF

T