




COLORADO OIL AND GAS CONSERVATION COMMISSION  
SUNDRY NOTICES AND REPORTS OF WELLS



OIL & GAS  
CONSERVATION COMMISSION

(Indicate nature of data by checking below)

- Notice of intention to drill XXXXXXXX
- Notice of intention to change plans \_\_\_\_\_
- Notice of date for test of water shut-off \_\_\_\_\_
- Report on result of test of water shut-off \_\_\_\_\_
- Notice of intention to re-drill or repair well \_\_\_\_\_
- Notice of intention to clean out well \_\_\_\_\_
- Statement of shooting \_\_\_\_\_
- Statement of perforating \_\_\_\_\_
- Notice to pull or otherwise alter casing \_\_\_\_\_
- Notice of intention to abandon well \_\_\_\_\_
- Report of work done on well since previous report \_\_\_\_\_

Following is a (notice of intention to do work) October 23 19 53  
(~~report of work done~~) (On land) (patented) described as follows:

Colorado Logan Merino  
State County Field

#1 State 21 C. SE NW 6N 54W 6th  
(Well No.) (Lease) (Sec. and 1/4 Sec.) (Twp.) (Range) (Meridian)

The well is located 1980 ft. (~~N~~) of N. Line and 1980 ft. (E) of W  
(S) (~~N~~)

Line of Sec. 21

To be furnished later.

The elevation above sea level is/ \_\_\_\_\_ ft.

Details of Plan of Work: (State names of and expected depths to objective sands; Show sizes, weights, and lengths of proposed casings; indicate mudding jobs, cementing points, and all other important proposed work.)

We propose to drill a well using rotary tools on the above described location, the well to be known as State #1.

It is expected that approximately 165 feet of 10-3/4" OD, 32.75#/ft., H-40, SRT casing will be landed and cemented to the surface. This well will be drilled to the "J" sand of the Dakota formation, which is expected at approximately 5100 feet.

If commercial production is encountered, a production string consisting of 5-1/2" OD 14# J-55, SRT., casing will be set thru the producing formation and cemented with 150 sacks of cement. The productive zone will then be perforated.

All measurements will be taken from the Kelly Bushing.

Approved: OCT 26 1953

A. J. Jensen  
Deputy Director

Company Trigood Oil Company

P. O. Box 1689  
Address Casper, Wyoming

By H. B. Gernert

H. B. Gernert  
Title General Manager

/ib SOI (3) fld, land, acctg, wf.  
Submit reports of proposed work, for approval, on this form in Duplicate for patented lands and in Triplicate for school and state lands.